EANCOM 2002 Syntax 3

Edition 2016_Update 2021

General purpose message
(GENRAL)

Introduction

The following message specification is based on the publication of the "General Purpose Message" of GS1 Global in syntax 3.

Status

MESSAGE TYPE: GENRAL
REFERENCE DIRECTORY: D.01B
EANCOM® SUBSET VERSION: 005

Definition

A message to enable the transmission of agreed textual information.

Principles

A General Message may be used to send general application support information to one or multiple addresses.

A General Message may be used to send required data for which there is no specific standard message.

A General Message MUST not be used as a substitute for an existing UNSM under development, under trial or at approved status or any EANCOM® subset of former UNSM's. Nor should it be used to avoid the development of a more specific application message.

The General Message is not designed or intended to be used as a replacement for existing electronic mail systems.

The General Message was designed primarily to:

- Facilitate early transmission testing between new EDI partners.

- Broadcasting of known problem areas to EDI partners.

- Transmission of text (preferably structured or coded) to supplement or further clarify previously transmitted EDI Standard Messages, e.g. to stress that previous data is for test purposes only or contains known errors to test out error routines.

- Transmission of small amounts of structured text where no existing message exists, e.g. computer listings.

Branching Diagram

|		
Tag	Tag = Segment/Group Tag	
St | MaxOcc	St = Status (M=Mandatory, C=Conditional, R=Required, O=Optional, A=Advised, D=Dependent)	
No	MaxOcc = Maximum occurrence of the segment/group; No = Consecutive segment number	

Branching Diagram

```
 ( 1 )
        ┌──────────────┐
        │     SG4      │
        ├───┬──────────┤
        │ C │    5     │
        ├───┴──────────┤
        │     CTA      │
        ├───┬──────────┤
        │ M │    1     │
        ├───┴──────────┤
        │     11       │
        └──────┬───────┘
               │
        ┌──────┴───────┐
        │     COM      │
        ├───┬──────────┤
        │ C │    9     │
        ├───┴──────────┤
        │     12       │
        └──────────────┘
```

Tag		Tag = Segment/Group Tag
St	MaxOcc	St = Status (M=Mandatory, C=Conditional, R=Required, O=Optional, A=Advised, D=Dependent)
	No	MaxOcc = Maximum occurrence of the segment/group; No = Consecutive segment number

© Copyright GS1 Germany GmbH · 4 · GS1_EN

Branching Diagram

```
  ( 2 )─────────────────┬──────────────┐
         │              │              │
         │          ┌───────────┐  ┌───────────┐
         │          │   UNT     │  │   UNZ     │
         │          │ M │   1   │  │ M │   1   │
         │          │    19     │  │    20     │
         │          └───────────┘  └───────────┘
     ┌───────────┐
     │   SG5     │
     │ C │  100  │
     │   FTX     │
     │ M │   1   │
     │    13     │
     └───────────┘
     ┌───────────┐
     │   SG6     │
     │ C │  100  │
     │   NAD     │
     │ M │   1   │
     │    14     │
     └───────────┘
         │
     ┌───────────┬───────────┐
 ┌───────────┐ ┌───────────┐
 │   SG7     │ │   SG8     │
 │ C │   10  │ │ C │   5   │
 │   RFF     │ │   CTA     │
 │ M │   1   │ │ M │   1   │
 │    15     │ │    17     │
 └───────────┘ └───────────┘
 ┌───────────┐ ┌───────────┐
 │   DTM     │ │   COM     │
 │ C │   10  │ │ C │   5   │
 │    16     │ │    18     │
 └───────────┘ └───────────┘
```

Tag		Tag = Segment/Group Tag
St	MaxOcc	St = Status (M=Mandatory, C=Conditional, R=Required, O=Optional, A=Advised, D=Dependent)
	No	MaxOcc = Maximum occurrence of the segment/group; No = Consecutive segment number

Message Structure

Seg.	No.	Status	Max Occ	Segment
UNA	1	C	1	Service string advice
UNB	2	M	1	Interchange header
General Message Heading Section				
UNH	3	M	1	Message header
BGM	4	M	1	Beginning of message
DTM	5	C	1	Date/time/period
SG1		C	10	RFF-DTM
RFF	6	M	1	Reference
DTM	7	C	10	Date/time/period
SG2		C	2	NAD-SG3-SG4
NAD	8	M	1	Name and address
SG3		C	10	RFF-DTM
RFF	9	M	1	Reference
DTM	10	C	10	Date/time/period
SG4		C	5	CTA-COM
CTA	11	M	1	Contact information
COM	12	C	9	Communication contact
General Message Detail Section				
SG5		C	100	FTX-SG6
FTX	13	M	1	Free text
SG6		C	100	NAD-SG7-SG8
NAD	14	M	1	Name and address
SG7		C	10	RFF-DTM
RFF	15	M	1	Reference
DTM	16	C	10	Date/time/period
SG8		C	5	CTA-COM
CTA	17	M	1	Contact information
COM	18	C	5	Communication contact
General Message Summary Section				
UNT	19	M	1	Message trailer
UNZ	20	M	1	Interchange trailer

Max. Occ. = Maximum occurrence of the segment/group, Status: M=Mandatory, C=Conditional, R=Required, O=Optional, A=Advised, D=Dependent

© Copyright GS1 Germany GmbH   6   GS1_EN

Segment Layout

No. Seg	St Max. Occ.
1 **UNA** C 1 Service string advice	
To define the characters selected for use as delimiters and indicators in the rest of the interchange that follows.	

Business Term	DE	EDIFACT	Format	St	*	Description
	UNA1	Component data element separator	an1	M	*	Used as a separator between component data elements contained within a composite data element (default value: ":")
	UNA2	Data element separator	an1	M	*	Used to separate two simple or composite data elements (default value: "+")
	UNA3	Decimal notation	an1	M	*	Used to indicate the character used for decimal notation (default value:".")
	UNA4	Release indicator	an1	M	*	Used to restore any service character to its original specification (value: "?").
	UNA5	Reserved for future use	an1	M	*	(default value: space)
	UNA6	Segment terminator	an1	M	*	Used to indicate the end of segment data (default value: " ' ")

The service string advice shall begin with the upper case characters UNA immediately followed by six characters in the order shown below. The same character shall not be used in more than one position of the UNA.

This segment is used to inform the receiver of the interchange that a set of service string characters which are different to the default characters are being used.

When using the default set of service characters, the UNA segment need not be sent. If it is sent, it must immediately precede the UNB segment and contain the four service string characters (positions UNA1, UNA2, UNA4 and UNA6) selected by the interchange sender.

Regardless of whether or not all of the service string characters are being changed every data element within this segment must be filled, (i.e., if some default values are being used with user defined ones, both the default and user defined values must be specified).

When expressing the service string characters in the UNA segment, it is not necessary to include any element separators.

The use of the UNA segment is required when using a character set other than level A.

Example:`UNA:+.? '`
Example:`UNA:+.? '`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   7   GS1_EN

Segment Layout

No. Seg		St Max. Occ.				
2	**UNB** M 1			Interchange header		
	To start, identify and specify an interchange.					

Business Term	DE	EDIFACT	Format	St	*	Description
	S001	Syntax identifier		M		See Part I chapter 5.2.7 and segment notes.
	0001	Syntax identifier	a4	M	*	UNOA UN/ECE level A UNOB UN/ECE level B UNOC UN/ECE level C UNOD UN/ECE level D UNOE UN/ECE level E UNOF UN/ECE level F
	0002	Syntax version number	n1	M	*	3 Version 3
	S002	Interchange sender		M		
	0004	Sender identification	an..35	M		GLN (n13)
	0007	Partner identification code qualifier	an..4	R	*	14 GS1
	0008	Address for reverse routing	an..14	O		
	S003	Interchange recipient		M		
	0010	Recipient identification	an..35	M		GLN (n13)
	0007	Partner identification code qualifier	an..4	R	*	14 GS1
	0014	Routing address	an..14	O		
	S004	Date/time of preparation		M		
	0017	Date of preparation	n6	M		YYMMDD
	0019	Time of preparation	n4	M		HHMM
	0020	Interchange control reference	an..14	M		Unique reference identifying the interchange. Created by the interchange sender.
	S005	Recipient's reference, password		O		
	0022	Recipient's reference/ password	an..14	M		
	0025	Recipient's reference/ password qualifier	an2	O		
	0026	Application reference	an..14	O		Message identification if the interchange contains only one type of message.
	0029	Processing priority code	a1	O		A Highest priority
	0031	Acknowledgement request	n1	O		1 Requested
	0032	Communications agreement ID	an..35	O	*	EANCOM......
	0035	Test indicator	n1	O		1 Interchange is a test

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

This segment is used to envelope the interchange, as well as to identify both, the party to whom the interchange is sent and the party who has sent the interchange. The principle of the UNB segment is the same as a physical envelope which covers one or more letters or documents, and which details, both the address where delivery is to take place and the address from where the envelope has come.

S001: The character encoding specified in basic code table of ISO/IEC 646 (7-bit coded character set for information interchange) shall be used for the interchange service string advice (if used) and up to and including the composite data element S001 'Syntax identifier' in the interchange header. The character repertoire used for the characters in an interchange shall be identified from the code value of data element 0001 in S001 'Syntax identifier' in the interchange header. The character repertoire identified does not apply to objects and/or encrypted data.

The default encoding technique for a particular repertoire shall be the encoding technique defined by its associated character set specification.

DE 0001: The recommended (default) character set for use in EANCOM® for international exchanges is character set A (UNOA). Should users wish to use character sets other than A, an agreement on which set to use should be reached on a bilateral basis before communications begin.

DE 0004, 0008, 0010, 0014, 0042 and 0046: Within EANCOM® the use of the Global Location Number (GLN) is recommended for the identification of the interchange sender and recipient.

DE 0008: Identification (e.g. a division) specified by the sender of the interchange, to be included if agreed, by the recipient in response interchanges, to facilitate internal routing.

DE 0042: Sub-level of sender internal identification, when further sub-level identification is required.

DE 0014: The address for routing, provided beforehand by the interchange recipient, is used by the interchange sender to inform the recipient of the internal address, within the latter's systems, to which the interchange should be routed. It is recommended that the GLN be used for this purpose.

DE 0007: Identification (e.g. a division) specified by the recipient of the interchange, to be included if agreed, by the sender in response interchanges, to facilitate internal routing.

DE 0046: Sub-level of recipient internal identification, when further sub-level identification is required.

DE S004: The date and time specified in this composite should be the date and time at which the interchange sender prepared the interchange. This date and time may not necessarily be the same as the date and time of contained messages.

DE 0020: The interchange control reference number is generated by the interchange sender and is used to identify uniquely each interchange. Should the interchange sender wish to re-use interchange control reference numbers, it is recommended that each number be preserved for at least a period of three months before being re-used. In order to guarantee uniqueness, the interchange control reference number should always be linked to the interchange sender's identification (DE 0004).

DE S005: The use of passwords must first be agreed bilaterally by the parties exchanging the interchange.

DE 0026: This data element is used to identify the application, on the interchange recipient's system, to which the interchange is directed. This data element may only be used if the interchange contains only one type of message, (e.g. only invoices). The reference used in this data element is assigned by the interchange sender.

DE 0031: This data element is used to indicate whether an acknowledgement to the interchange is required. The EANCOM® APERAK or CONTRL message should be used to provide acknowledgement of interchange receipt. In addition, the EANCOM® CONTRL message may be used to indicate when an interchange has been rejected due to syntax errors.

DE 0032: This data element is used to identify any underlying agreements which control the exchange of data. Within EANCOM® , the identity of such agreements must start with the letters 'EANCOM', the remaining characters within the data element being filled according to bilateral

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

agreements.

Example: `UNB+UNOA:3+4012345000009:14:1+4000004000002:14:4000004000099+021013:1043+12345555+`
        `REF:AA++A+1+EANCOM-DISI+1'`

Example: `UNB+UNOA:3+5412345678908:14+8798765432106:14+020102:1000+12345555+++++EANCOMREF`
        `52'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   10   GS1_EN

Segment Layout

No. Seg	St	Max. Occ.					
3 **UNH** M 1 Message header							
To head, identify and specify a message.							

Business Term	DE	EDIFACT	Format	St	*	Description
	0062	Message reference number	an..14	M		Senders unique message reference. Sequence number of messages in the interchange. DE 0062 in the UNT will have the same value. This number is generated by the sender.
	S009	Message identifier		M		
	0065	Message type	an..6	M	*	GENRAL General purpose message
	0052	Message version number	an..3	M	*	D Draft version/ UN/EDIFACT Directory
	0054	Message release number	an..3	M	*	01B Release 2001 - B
	0051	Controlling agency	an..2	M	*	UN UN/CEFACT
	0057	Association assigned code	an..6	R	*	EAN005 GS1 version control number (GS1 Permanent Code)

This segment is used to head, identify and specify a message.
DE's 0065, 0052, 0054, and 0051: Indicate that the message is a UNSM General message based on the D.01B directory under the control of the United Nations.
Example:

Example: `UNH+1+GENRAL:D:01B:UN:EAN005'`
Example: `UNH+ME000001+GENRAL:D:01B:UN:EAN005'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   11   GS1_EN

Segment Layout

No. Seg		St Max. Occ.				
4 **BGM** M 1				Beginning of message		
To indicate the type and function of a message and to transmit the identifying number.						

Business Term	DE	EDIFACT	Format	St	*	Description
	C002	Document/message name		R		
	1001	Document name code	an..3	R	*	719 General message
	1131	Code list identification code	an..17	N		
	3055	Code list responsible agency code	an..3	R	*	9 GS1
	1000	Document name	an..35	O		
	C106	Document/message identification		R		
	1004	Document identifier	an..35	R		General Message Number assigned by the sender
	1225	Message function code	an..3	R	*	9 Original
	4343	Response type code	an..3	D		AC Acknowledge - with detail and change AI Acknowledge only changes NA No acknowledgement needed This DE is used if the general message issuer wishes to explicitly indicate whether an acknowledgement is required or not.

This segment is used to indicate the type and function of a message and to transmit the identifying number.
All references other than the document number DE 1004 are in the RFF segment.
Example:

Example: `BGM+719::9:A+1+9+AA'`
Example: `BGM+719::9+GE282+9'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

No. Seg		St Max. Occ.				
5 **DTM** C 1 Date/time/period						
To specify date, and/or time, or period.						

Business Term	DE	EDIFACT	Format	St	*	Description
	C507	Date/time/period		M		
	2005	Date or time or period function code qualifier	an..3	M	*	137 Document/ message date/ time
	2380	Date or time or period value	an..35	R		
	2379	Date or time or period format code	an..3	R		102 CCYYMMDD 718 CCYYMMDD- CCYYMMDD

This segment is used to specify the date of the General message.
DE 2005: Identification of the 'Document/message date/time' (code value 137) is mandatory in an EANCOM message.
Example:

Example: `DTM+137:19930906:102'`
Example: `DTM+137:20020106:102'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH 13 GS1_EN

Segment Layout

No. Seg	St Max. Occ.		
SG1 C 10	RFF-DTM		
A group of segments giving references where necessary, their dates relating to the whole message, e.g. despatch advice, contract number.			
RFF M 1	Reference		
To specify a reference.			

Business Term	DE	EDIFACT	Format	St	*	Description
	C506	Reference		M		
	1153	Reference code qualifier	an..3	M		CT Contract number IV Invoice number ON Order number (buyer) PL Price list number
	1154	Reference identifier	an..70	R		

This segment is used to specify references which relate to the, for example, Purchase Order Numbers.
Example:

Example: `RFF+BC:1'`
Example: `RFF+ON:930625'`

(Segment 6)

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   14   GS1_EN

Segment Layout

No. Seg	St	Max. Occ.		

SG1	C	10		RFF-DTM

A group of segments giving references where necessary, their dates relating to the whole message, e.g. despatch advice, contract number.

7

DTM	C	10		Date/time/period

To specify date, and/or time, or period.

Business Term	DE	EDIFACT	Format	St	*	Description
	C507	Date/time/period		M		
	2005	Date or time or period function code qualifier	an..3	M	*	171 Reference date/ time
	2380	Date or time or period value	an..35	R		
	2379	Date or time or period format code	an..3	R		102 CCYYMMDD 718 CCYYMMDD- CCYYMMDD

This segment is used to specify dates relating to the references given in the previous RFF segment. Example:

Example: DTM+171:19930827:102'
Example: DTM+171:20020827:102'

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   15   GS1_EN

Segment Layout

No. Seg	St Max. Occ.

8	**SG2** C 2 NAD-SG3-SG4					

A group of segments identifying names, addresses and locations, and referred documents relevant for the whole Genral message.

NAD   M 1   Name and address

To specify the name/address and their related function, either by C082 only and/or unstructured by C058 or structured by C080 thru 3207.

Business Term	DE	EDIFACT	Format	St	*	Description
	3035	Party function code qualifier	an..3	M		FR Message from MR Message recipient
	C082	Party identification details		A		
	3039	Party identifier	an..35	M		
	1131	Code list identification code	an..17	N		
	3055	Code list responsible agency code	an..3	R	*	9 GS1
	C058	Name and address		O		This composite may only be used to fulfill the requirements of directive 2003/58/EC, article 4.
	3124	Name and address description	an..35	M		
	3124	Name and address description	an..35	O		
	3124	Name and address description	an..35	O		
	3124	Name and address description	an..35	O		
	3124	Name and address description	an..35	O		
	C080	Party name		D		
	3036	Party name	an..35	M		Party Name in clear text.
	3036	Party name	an..35	O		
	3036	Party name	an..35	O		
	3036	Party name	an..35	O		
	3036	Party name	an..35	O		
	3045	Party name format code	an..3	O		
	C059	Street		D		
	3042	Street and number or post office box identifier	an..35	M		Building Name/Number and Street
	3042	Street and number or post office box identifier	an..35	O		Name and/or P.O. Box.
	3042	Street and number or post office box identifier	an..35	O		

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

Business Term	DE	EDIFACT	Format	St	*	Description
	3042	Street and number or post office box identifier	an..35	O		
	3164	City name	an..35	D		City/Town name, clear text
	C819	Country sub-entity details		D		
	3229	Country sub-entity name code	an..9	O		
	1131	Code list identification code	an..17	O		
	3055	Code list responsible agency code	an..3	O		
	3228	Country sub-entity name	an..70	O		County/State, clear text.
	3251	Postal identification code	an..17	D		Postal Code
	3207	Country name code	an..3	D		ISO 3166 two alpha code

This segment is used to identify the trading parties involved in the general message. Identification of the sender and receiver of the general message is mandatory.
Example:
Dependency Notes:
The following composites and data elements are only used when a coded name and address can not be used. The affected composites and data elements are as follows:
    C080 - C059 - 3164 - C819 - 3251 - 3207

Example: NAD+BY+5412345000013::9+X::::X+A:A:A:A:S:1+A:A:A:X+A+A:23:2:X+A+GB'
Example: NAD+FR+5456789000017::9'
Example: NAD+MR+3323456007896::9'

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

No. Seg	St Max. Occ.	
SG2 C 2	NAD-SG3-SG4	

A group of segments identifying names, addresses and locations, and referred documents relevant for the whole Genral message.

SG3 C 10 RFF-DTM

A group of segments giving references only relevant to the specified party rather than to the whole message.

9 **RFF** M 1 Reference

To specify a reference.

Business Term	DE	EDIFACT	Format	St	*	Description
	C506	Reference		M		
	1153	Reference code qualifier	an..3	M	*	FC Fiscal number GN Government reference number VA VAT registration number YC1 Additional party identification (GS1 Temporary Code)
	1154	Reference identifier	an..70	R		

This segment is used to specify reference numbers related to the party identified in the previous NAD segment, e.g., Vat Registration Numbers.
Example:

Example: `RFF+VA:55344212'`
Example: `RFF+VA:VR123554'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

No. Seg		St	Max. Occ.	

SG2 C 2 NAD-SG3-SG4

A group of segments identifying names, addresses and locations, and referred documents relevant for the whole Genral message.

SG3 C 10 RFF-DTM

A group of segments giving references only relevant to the specified party rather than to the whole message.

10 **DTM** C 10 Date/time/period

To specify date, and/or time, or period.

Business Term	DE	EDIFACT	Format	St	*	Description
	C507	Date/time/period		M		
	2005	Date or time or period function code qualifier	an..3	M	*	171 Reference date/ time
	2380	Date or time or period value	an..35	R		
	2379	Date or time or period format code	an..3	R		102 CCYYMMDD 718 CCYYMMDD- CCYYMMDD

This segment is used to specify dates relating to the references given in the previous RFF segment. Example:

Example: `DTM+171:19930101:102'`
Example: `DTM+171:20020827:102'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   19   GS1_EN

Segment Layout

No. Seg	St Max. Occ.

SG2 C 2   NAD-SG3-SG4

A group of segments identifying names, addresses and locations, and referred documents relevant for the whole Genral message.

SG4 C 5   CTA-COM

A group of segments giving contacts details of the specific person or department within the party identified in the NAD segment.

11 **CTA** M 1   Contact information

To identify a person or a department to whom communication should be directed.

Business Term	DE	EDIFACT	Format	St	*	Description
	3139	Contact function code	an..3	R		PM Product management contact SA Sales administration SR Sales representative or department
	C056	Department or employee details		O		
	3413	Department or employee name code	an..17	O		
	3412	Department or employee name	an..35	O		

This segment may be used to identify the department and/or person within the party specified in the NAD.
The Global Location Number GLN is particularly suitable for this purpose.
Example:

Example: `CTA+AD+ACCOUNTS:GEORGE BERRY'`
Example: `CTA+SA+:GEORGE BERRY'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

No. Seg	St	Max. Occ.	

SG2	C 2	NAD-SG3-SG4	

A group of segments identifying names, addresses and locations, and referred documents relevant for the whole Genral message.

SG4	C 5	CTA-COM	

A group of segments giving contacts details of the specific person or department within the party identified in the NAD segment.

12

COM	C 9	Communication contact	

To identify a communication number of a department or a person to whom communication should be directed.

Business Term	DE	EDIFACT	Format	St	*	Description
	C076	Communication contact		M		
	3148	Communication address identifier	an..51	M		
	3155	Communication address code qualifier	an..3	M		AO Uniform Resource Location (URL) EM Electronic mail TE Telephone

This segment is used to identify the communications number and the type of communications used for the person or department identified in the CTA segment.
Example:

Example: `COM+00447185644221:TE'`
Example: `COM+00447188755112:TE'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

No. Seg	St Max. Occ.

	SG5	C 100	FTX-SG6
	A group of segments enabling the specification of the text and optionally, the identification of other parties or location to whom the information should be directed.		
13	FTX	M 1	Free text
	To provide free form or coded text information.		

Business Term	DE	EDIFACT	Format	St	*	Description
	4451	Text subject code qualifier	an..3	M		ADK Promotion information INV Invoice instruction ITS Testing instructions ORI Order instruction PRD Product information PUR Purchasing information
	4453	Free text function code	an..3	O		1 Text for subsequent use 2 Text replacing missing code 3 Text for immediate use
	C107	Text reference		D		References to a standard text. This composite is only used when trading partners have agreed to use mutually defined code values.
	4441	Free text value code	an..17	M		001 = ...Standard text...
	1131	Code list identification code	an..17	O		
	3055	Code list responsible agency code	an..3	D		91 Assigned by supplier or supplier's agent 92 Assigned by buyer or buyer's agent
	C108	Text literal		D		This composite is only used if coded text can not be used.
	4440	Free text value	an..51	M		
	4440	Free text value	an..51	O		
	4440	Free text value	an..51	O		
	4440	Free text value	an..51	O		
	4440	Free text value	an..51	O		
	3453	Language name code	an..3	D		ISO 639 two alpha code This data element is only used when non coded free text has been provided in data element C108.

This segment is used to provide free text or coded information. The detail section of the general message is formed by a repeating group of segments always starting with the FTX segment. Each FTX segment corresponds to different textual information.

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

Use of this segment in free form may inhibit automatic processing of the general message. Coded reference to standard texts is an available functionality which enables automatic processing and reduces transmission overheads. Standard texts should be mutually defined among trading partners and can be used to cover legal or other requirements.
Example:

Example: `FTX+AAA+1+001:23:91+A:A:A:A:A+EN'`
Example: `FTX+ADK+1++OUR STOREWIDE SPRING SALE WILL START NEXT WEEK:ALL ITEMS 10 TO 30 % OFF'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   23   GS1_EN

Segment Layout

No. Seg		St	Max. Occ.	

SG5 C 100 FTX-SG6

A group of segments enabling the specification of the text and optionally, the identification of other parties or location to whom the information should be directed.

SG6 C 100 NAD-SG7-SG8

A group of segments allowing the specification of the name and address of a party, within the receiving party identified in the heading section, to whom the preceding text should be distributed. It also allows to specify the name and address of a party advised as copyreader of this text.

14

NAD M 1 Name and address

To specify the name/address and their related function, either by C082 only and/or unstructured by C058 or structured by C080 thru 3207.

Business Term	DE	EDIFACT	Format	St	*	Description
	3035	Party function code qualifier	an..3	M	*	NI Notify party
	C082	Party identification details		A		
	3039	Party identifier	an..35	M		
	1131	Code list identification code	an..17	N		
	3055	Code list responsible agency code	an..3	R	*	9 GS1
	C058	Name and address		O		This composite may only be used to fulfill the requirements of directive 2003/58/EC, article 4.
	3124	Name and address description	an..35	M		
	3124	Name and address description	an..35	O		
	3124	Name and address description	an..35	O		
	3124	Name and address description	an..35	O		
	3124	Name and address description	an..35	O		
	C080	Party name		D		
	3036	Party name	an..35	M		Party Name in clear text.
	3036	Party name	an..35	O		
	3036	Party name	an..35	O		
	3036	Party name	an..35	O		
	3036	Party name	an..35	O		
	3045	Party name format code	an..3	O		
	C059	Street		D		
	3042	Street and number or post office box identifier	an..35	M		Building Name/Number and Street

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

Business Term	DE	EDIFACT	Format	St	*	Description
	3042	Street and number or post office box identifier	an..35	O		Name and/or P.O. Box.
	3042	Street and number or post office box identifier	an..35	O		
	3042	Street and number or post office box identifier	an..35	O		
	3164	City name	an..35	D		City/Town name, clear text.
	C819	Country sub-entity details		D		
	3229	Country sub-entity name code	an..9	O		
	1131	Code list identification code	an..17	O		
	3055	Code list responsible agency code	an..3	O		
	3228	Country sub-entity name	an..70	O		County/State, clear text.
	3251	Postal identification code	an..17	D		Postal Code
	3207	Country name code	an..3	D		ISO 2 Alpha Code.

This segment is used to identify any parties who must be notified on the content of the message contained in the previous FTX segment.
Example:
Dependency Notes:
The following composites and data elements are only used when a coded name and address can not be used. The affected composites and data elements are as follows:
    C080 - C059 - 3164 - C819 - 3251 - 3207

Example: NAD+NI+1::9+X::::X+A:A:A:A:A:1+A:A:A:X+A+A:23:2:X+A+GB'
Example: NAD+NI+3323456001238::9'

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   25   GS1_EN

Segment Layout

No. Seg	St	Max. Occ.	

SG5   C 100   FTX-SG6

A group of segments enabling the specification of the text and optionally, the identification of other parties or location to whom the information should be directed.

SG6   C 100   NAD-SG7-SG8

A group of segments allowing the specification of the name and address of a party, within the receiving party identified in the heading section, to whom the preceding text should be distributed. It also allows to specify the name and address of a party advised as copyreader of this text.

SG7   C 10   RFF-DTM

A group of segments giving references only relevant to the specified party rather than the whole message.

15   **RFF**   M 1   Reference

To specify a reference.

Business Term	DE	EDIFACT	Format	St	*	Description
	C506	Reference		M		
	1153	Reference code qualifier	an..3	M		PD Promotion deal number
	1154	Reference identifier	an..70	R		

This segment is used to specify any references relevant to the party identified in the previous NAD segment.
Example:

Example: `RFF+PD:1'`
Example: `RFF+PD:324FEB97'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

No. Seg	St Max. Occ.

SG5 C 100 FTX-SG6

A group of segments enabling the specification of the text and optionally, the identification of other parties or location to whom the information should be directed.

SG6 C 100 NAD-SG7-SG8

A group of segments allowing the specification of the name and address of a party, within the receiving party identified in the heading section, to whom the preceding text should be distributed. It also allows to specify the name and address of a party advised as copyreader of this text.

SG7 C 10 RFF-DTM

A group of segments giving references only relevant to the specified party rather than the whole message.

16 **DTM** C 10 Date/time/period

To specify date, and/or time, or period.

Business Term	DE	EDIFACT	Format	St	*	Description
	C507	Date/time/period		M		
	2005	Date or time or period function code qualifier	an..3	M	*	171 Reference date/ time
	2380	Date or time or period value	an..35	R		
	2379	Date or time or period format code	an..3	R		102 CCYYMMDD 718 CCYYMMDD-CCYYMMDD

This segment is used to specify any dates related to the references provided in the previous RFF segment.
Example:

Example: `DTM+171:19930101:102'`
Example: `DTM+171:20020101:102'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

No.	Seg	St	Max. Occ.	

SG5 C 100 FTX-SG6

A group of segments enabling the specification of the text and optionally, the identification of other parties or location to whom the information should be directed.

SG6 C 100 NAD-SG7-SG8

A group of segments allowing the specification of the name and address of a party, within the receiving party identified in the heading section, to whom the preceding text should be distributed. It also allows to specify the name and address of a party advised as copyreader of this text.

SG8 C 5 CTA-COM

A group of segments giving contact details of the specific person or department within the party identified in the NAD segment.

17 **CTA** M 1 Contact information

To identify a person or a department to whom communication should be directed.

Business Term	DE	EDIFACT	Format	St	*	Description
	3139	Contact function code	an..3	R		PM Product management contact SA Sales administration SR Sales representative or department
	C056	Department or employee details		O		
	3413	Department or employee name code	an..17	O		
	3412	Department or employee name	an..35	O		

This segment is used to identify the department and/or person within the party specified in the NAD.
The Global Location Number GLN is particularly suitable for this purpose.
Example:

Example: `CTA+AA+1:1'`
Example: `CTA+PM+:MARY DECKER'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   28   GS1_EN

Segment Layout

No. Seg	St Max. Occ.		
SG5	C 100	FTX-SG6	
A group of segments enabling the specification of the text and optionally, the identification of other parties or location to whom the information should be directed.			
SG6	C 100	NAD-SG7-SG8	
A group of segments allowing the specification of the name and address of a party, within the receiving party identified in the heading section, to whom the preceding text should be distributed. It also allows to specify the name and address of a party advised as copyreader of this text.			
SG8	C 5	CTA-COM	
A group of segments giving contact details of the specific person or department within the party identified in the NAD segment.			
18 **COM**	C 5	Communication contact	
To identify a communication number of a department or a person to whom communication should be directed.			

Business Term	DE	EDIFACT	Format	St	*	Description
	C076	Communication contact		M		
	3148	Communication address identifier	an..51	M		
	3155	Communication address code qualifier	an..3	M		AO Uniform Resource Location (URL) EM Electronic mail TE Telephone

This segment is used to identify the communications number and the type of communications used for the person or department identified in the CTA segment.
Example:

Example: `COM+1:TE'`
Example: `COM+00447188433211:FX'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

Segment Layout

No. Seg		St	Max. Occ.				
19	**UNT**	M	1	Message trailer			
				To end and check the completeness of a message.			

Business Term	DE	EDIFACT	Format	St	*	Description
	0074	Number of segments in the message	n..6	M		The total number of segments in the message is specified here.
	0062	Message reference number	an..14	M		The message reference numbered detailed here should equal the one specified in the UNH segment.

This segment is a mandatory UN/EDIFACT segment. It must always be the last segment in the message.
Example:

Example: `UNT+17+1'`
Example: `UNT+17+ME000001'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   30   GS1_EN

Segment Layout

No. Seg		St Max. Occ.				
20 **UNZ**		M 1	Interchange trailer			
To end and check the completeness of an interchange.						

Business Term	DE	EDIFACT	Format	St	*	Description
	0036	Interchange control count	n..6	M		Number of messages or functional groups within an interchange.
	0020	Interchange control reference	an..14	M		Identical to DE 0020 in UNB segment.

This segment is used to provide the trailer of an interchange.
DE 0036: If functional groups are used, this is the number of functional groups within the interchange. If functional groups are not used, this is the number of messages within the interchange.

Example: `UNZ+1+12345555'`
Example: `UNZ+5+12345555'`

Max. Occ. = Maximum Occurrence, St = Status, * = Restricted Codes
Status: M=Mandatory, R=Required, O=Optional, C=Conditional, D=Dependent, A=Advised, N=Not used

© Copyright GS1 Germany GmbH   31   GS1_EN

Used Codes

0001	Syntax identifier
	Coded identification of the agency controlling a syntax and syntax level used in an interchange.
	Notes: 1. a3, upper case, Controlling Agency (e.g. UNO=UN/ECE) and a1 stating level (e.g. A) (which together give UNOA).
UNOA	UN/ECE level A
	As defined in the basic code table of ISO 646 with the exceptions of lower case letters, alternative graphic character allocations and national or application-oriented graphic character allocations.
UNOB	UN/ECE level B
	As defined in the basic code table of ISO 646 with the exceptions of alternative graphic character allocations and national or application-oriented graphic character allocations.
UNOC	UN/ECE level C
	As defined in ISO/IEC 8859-1 : Information technology - Part 1: Latin alphabet No. 1.
UNOD	UN/ECE level D
	As defined in ISO/IEC 8859-2 : Information technology - Part 2: Latin alphabet No. 2.
UNOE	UN/ECE level E
	As defined in ISO/IEC 8859-5 : Information technology - Part 5: Latin/Cyrillic alphabet.
UNOF	UN/ECE level F
	As defined in ISO 8859-7 : Information processing - Part 7: Latin/Greek alphabet.
0002	Syntax version number
	Version number of the syntax identified in the syntax identifier (0001)
	Notes: 1. Increments 1 for each version.
3	Version 3
	ISO 9735 Amendment 1:1992.
	GS1 Description: Syntax version number 3. This code can be used with all of the character sets (A, B, C, D, E and F).

Used Codes

0007
Partner identification code qualifier
Qualifier referring to the source of codes for the identifiers of interchanging partners.

Notes:
1. Used with sender/recipient identification code.

14
GS1
Partner identification code assigned by GS1, an international organization of GS1 Member Organizations that manages the GS1 System.

0025
Recipient's reference/password qualifier
Qualifier for the recipient's reference or password.

Notes:
1. If specified in IA.

AA
Reference
Recipient's reference/password is a reference.

BB
Password
Recipient's reference/password is a password.

0029
Processing priority code
Code determined by the sender requesting processing priority for the interchange.

Notes:
1. Used if specified in IA.

A
Highest priority
Requested processing priority is the highest.

0031
Acknowledgement request
Code determined by the sender for acknowledgement of the interchange.

Notes:
1. Set = 1 if sender requests acknowledgement, i.e. UNB and UNZ segments received and identified.

1
Requested
Acknowledgement is requested.

0035
Test indicator
Indication that the interchange is a test.

Notes:
1. Set = 1 if the interchange is a test. Otherwise not used.

Used Codes

1	Interchange is a test Indicates that the interchange is a test.
5	Interchange is a service provider test Indicates that this interchange is a test with a service provider.

0051	Controlling agency Code to identify the agency controlling the specification, maintenance and publication of the message type.
UN	UN/CEFACT United Nations Centre for Trade Facilitation and Electronic Business (UN/CEFACT). GS1 Description: UN Economic Commission for Europe (UN/ECE), Committee on the development of trade (TRADE), Working Party on facilitation of international trade procedures (WP.4).

0052	Message version number Version number of a message type. Notes: 1. If UNG/UNE is used, shall be identical in UNG and UNE. The representation of 0052 was specified as n..3 in version 1 of ISO 9735.
D	Draft version/UN/EDIFACT Directory Message approved and issued as a draft message (Valid for directories published after March 1993 and prior to March 1997). Message approved as a standard message (Valid for directories published after March 1997).

0054	Message release number Release number within the current message type version number (0052). Notes: 1. The representation of 0054 was specified as n..3 in version 1 of ISO 9735.
01B	Release 2001 - B Message approved and issued in the second 2001 release of the UNTDID (United Nations Trade Data Interchange Directory).

0057	Association assigned code A code assigned by the association responsible for the design and maintenance of the message type concerned, which further identifies the message.
EAN005	GS1 version control number (GS1 Permanent Code) Indicates that the message is an EANCOM message in version 005.

Used Codes

0065   Message type
Code identifying a type of message and assigned by its controlling agency.

Notes:
1. Type of message being transmitted.

GENRAL   General purpose message
A code to identify the general purpose message.
GS1 Description:
A message to enable the transmission of textual information.

1001   Document name code
Code specifying the document name.

719   General message
Document/message providing agreed textual information.
GS1 Note: Replaces GS1 Temporary Code 14E.

1131   Code list identification code
Code identifying a user or association maintained code list.

Notes:
1. The codes for this data element are provided by the code list responsible agency defined in data element 3055.

23   Clearing house automated payment
Self explanatory.

Notes:
This code value will be removed effective with directory D.04A.
GS1 Description:
Banking community' automated payment clearing system.

25   Bank identification
Code for identification of banks.

Notes:
This code value will be removed effective with directory D.04A.

106   Incoterms 1980
(4110) Code to indicate applicable Incoterm (1980 edition) under which seller undertakes to deliver merchandise to buyer (ICC). Incoterms 1990: use 4053 only.

Notes:
This code value will be removed effective with directory D.04A.

132   Charge
Identification of a type of charge.

Notes:
This code value will be removed effective with directory D.04A.

Used Codes

154	Bank branch sorting identification
	Identification of a specific branch of a bank.
	Notes:
	This code value will be removed effective with directory D.04A.
157	Clearing code
	Identification of the responsible bank/clearing house which has cleared or is ordered to do the clearing.
	Notes:
	This code value will be removed effective with directory D.04A.
166	Social security identification
	Code assigned by the authority competent to issue social security identification to identify a person.
	Notes:
	This code value will be removed effective with directory D.04A.
174	Citizen identification
	Self explanatory.
	Notes:
	This code value will be removed effective with directory D.04A.
	GS1 Description:
	Code issued by national authority competent to issue citizen identification to identify a person.
1E	Incoterms 1990 (GS1 Temporary Code)
	Incoterms 1990 as published by the International Chamber of Commerce (ICC).
2E	Incoterms 2000 (GS1 Temporary Code)
	Incoterms 2000 as published by the International Chamber of Commerce (ICC).
3E	Incoterms 2010 (GS1 Temporary Code)
	Incoterms 2010 as published by the International Chamber of Commerce (ICC).
ADR	Accord Europeen au transport international dangereuses (GS1 Temporary Code)
	A European agreement concerning the international carriage of dangerous goods by road.
BR	Brand (GS1 Temporary Code)
	An identifying mark or label on the products of a particular company, or the kind or make of a commodity.
CA	Category (GS1 Temporary Code)
	A class or division in a scheme of classification.

Used Codes

CO	Colour (GS1 Temporary Code) Description of the colour required/available on the goods.
FL	Flavor (GS1 Temporary Code) The characteristic quality of goods.
HMT	Hazardous material standard text (GS1 Temporary Code) Code indicating agreed standard text on hazardous materials.
LOC	Location Code (GS1 Temporary Code) This is a code to indicate where the EAS tag is located on the Trade Item. Values include On outside of Trade Item, Concealed inside Trade Item, Integrated Inside Trade Item.
OAG	Organic Claim Agency (GS1 Temporary Code) A governing body that creates and maintain standards related to organic products.
OCO	Organic Trade Item Code (GS1 Temporary Code) Used to indicate the organic status of a trade item or of one or more of its components.
OUM	Ordering unit of measure (GS1 Temporary Code) The alternate Unit of Measure of how Trade Items are ordered by the Retailer under one Unit of Measure, but sold under another Unit of Measure.
SKB	SKRS recommendation (GS1 Temporary Code) SKRS recommendation for standard clothes hanger.
SRN	Service relation number (GS1 Temporary Code) A number used to identify a database entry which records recurring services, e.g., treatment of a patient in a hospital, usage by a member of a library facilities, etc.
ST	Style (GS1 Temporary Code) Specific or characteristic design in any goods.
SUM	Selling unit of measure (GS1 Temporary Code) Describes the measurement used for selling unit of the Trade Item to the end consumer.
SZ	Size (GS1 Temporary Code) Any of a series of graded classifications of measure into which goods are divided.
SZG	Size Group (GS1 Temporary Code) A description of the variable size that is necessary to uniquely specify the size of the item in conjunction with the nonpackaged size dimension.
TYP	Type Code (GS1 Temporary Code) This is a code to indicate the type of EAS tag located on the Trade Item. Values include Acousto-Magnetic, Electro-Magnetic, Ink or dye, Microwave, Radio Frequency.

Used Codes

X11	Diet Allergen (GS1 Temporary Code) Indication of which dietary or allergen marks that are on the package.
X12	Environment (GS1 Temporary Code) Indication of which environmental marks (e.g. recycling schemes) that are on trade item package.
X13	Ethical (GS1 Temporary Code) Indication of which ethical trading marks that are on the package.
X14	Free Form (GS1 Temporary Code) Indication of which free-from marks that are on the package.
X15	Expiration date (GS1 Temporary Code) Indicates the type of expiration date marked on the packaging.
X16	Nesting Direction (GS1 Temporary Code) Depicts the arrangement of two items that nest together specifically whether they nest against each other or on top of each other.
X17	Package Marks Hygienic (GS1 Temporary Code) Indication of which hygiene markings are present in the product package
X18	Hazardous Components are Removable (GS1 Temporary Code) An indicator if any hazardous components contained within the trade item can easily be separated from the other materials to facilitate product recycling.
X19	Trade Item Has Refuse Obligations (GS1 Temporary Code) Indicates if there are special disposal obligations that apply to the trade item for example INTRASTAT.
X20	Trade Item Is Designed for Easy Disassembly (GS1 Temporary Code) Indicates that the trade item is designed for easy disassembly by recycling facilities using standard industry tools.
X21	Trade Item Is Rigid Plastic Packaging Container (GS1 Temporary Code) Indicates that a product is or is contained in a Rigid Plastic Packaging Container (RPPC) as defined by laws in the target market.
X22	Trade Item Is ROHS Compliant (GS1 Temporary Code) Indicates if the product is compliant with the European Union RoHS Directive.
X23	Trade Item Is Universal Waste (GS1 Temporary Code) Indicates if a product can be considered universal waste.
X24	Trade Item Is Consumer Upgradeable Or Maintainable (GS1 Temporary Code) Indicates if a product can be easily upgraded or have parts replaced by the consumer.
X25	Trade Item Contains Short Chain Chlorinated Paraffins (GS1 Temporary Code) Indicate if the trade item and/or its components contain paints, coatings, plastics or other materials containing short chain chlorinated paraffins (SCCPs).

Used Codes

X26	Trade Item Contains Pesticide (GS1 Temporary Code)
	Indicates if the trade item is advertised or labelled as a chemical or contains a chemical that is advertised or labelled to kill, repel or prevent the growth of any living organism.
X27	Trade Item Contains Propellant (GS1 Temporary Code)
	Indicates if a trade item contains a compressed gas or propellant.
X28	Trade Item Contains Polyvinyl Chloride (GS1 Temporary Code)
	Indicate if product contains Polyvinyl Chloride (PVC), a widely used thermoplastic polymer.
X29	Trade Item Chemical Is Not Intended For Human Consumption (GS1 Temporary Code)
	Indicates that the trade item is or contains a Liquid, Gel, Paste, Powder, or Flammable solid not intended for human consumption (ingested).
X30	ROHS Compliance Failure Material (GS1 Temporary Code)
	The material used in the trade item that does not comply with the ROHS Directives
X31	Packaging Terms And Condition (GS1 Temporary Code)
	Indicates if the packaging given in the described packaging configuration is a rented, exchangeable, against deposit or one way/not reusable.
X32	Warranty Effective Date Type (GS1 Temporary Code)
	The type of date associated with the warranty trade item usually expressed as an event date for the item for example date of purchase, date of manufacture or date of delivery.
X33	Warranty Type (GS1 Temporary Code)
	Type of warranty available for the part, e.g. labour, distance, extended service.
X35	Warranty Constraint (GS1 Temporary Code)
	Defines the relationship between different guarantee terms, e.g. "and", "or", "the stronger", "the weaker".
X36	Seasonal Availability End Date (GS1 Temporary Code)
	Indicates the end date of the trade item's seasonal availability.
X37	Seasonal Availability Start Date (GS1 Temporary Code)
	Indicates the start date of the trade item's seasonal availability.
X38	Season Calendar Year (GS1 Temporary Code)
	This element indicates the calendar year in which the trade item is seasonally available.
X39	Season Parameter (GS1 Temporary Code)
	Indication of the season, in which the trade item is available.
X40	Trade Item Automatic Power Down is Enabled (GS1 Temporary Code)
	An indicator whether a product is enabled with auto power down feature when shipped to the customer.

Used Codes

X41	**Electrical Usage Agency Code (GS1 Temporary Code)** The agency that regulates electrical usage for products within a target market.
X42	**Nesting Type (GS1 Temporary Code)** Depicts whether a nested item fits inside or over the other item in a nesting relationship.
X43	**Display Dimension Type Code (GS1 Temporary Code)** Depicts certain display scenarios used for measurement.
X44	**Manufacturer Has Take Back Program (GS1 Temporary Code)** Indicates if the manufacturer of the trade item offers any take back programs to consumers for the product to be reused, remanufactured or recycled by the manufacturer.
X45	**Display Resolution (GS1 Temporary Code)** The display resolution of a television or computer display.
X46	**Orientation Preference Sequence (GS1 Temporary Code)** Depicts the preferred sequence of orientation used to communicate the manufacturers relative preferences of orientation.
X47	**Orientation Type (GS1 Temporary Code)** Depicts via code a display orientation for a trade item.
X48	**Electrical Usage Trade Item Classification Code (GS1 Temporary Code)** A classification code value from a product classification scheme provided to drive required information for electrical usage.
X49	**Electrical Usage Trade Item Classification Name (GS1 Temporary Code)** A classification name from a product classification scheme provided to drive required information for electrical usage.
X50	**Electrical Usage SubClassification Code (GS1 Temporary Code)** A sub-classification code value from a product classification scheme provided to drive required information for electrical usage.
X51	**Electrical Usage SubClassification Name (GS1 Temporary Code)** A sub-classification name provided to drive required information for electrical usage.
X52	**Confirmation Status Code (GS1 Temporary Code)** The CIC Confirmation Code must be of a type of code number that can be generated automatically by a computer system.
X53	**Confirmation Status Code Description (GS1 Temporary Code)** Provides the code description that matches up with the Code that can possibly be generated automatically by a computer system.
X54	**Additional Confirmation Status Description (GS1 Temporary Code)** Provides a way to communicate human entered information that may not be covered by the machine to machine codes and descriptions.

Used Codes

X55	Corrective Action (GS1 Temporary Code) Provides the corrective action code to fix the issue that caused the problem.
X56	Expected Corrective Information (GS1 Temporary Code) Provides the expected corrective information via a human entered information that may not be covered by the machine to machine codes.
X57	Electrical Usage Trade Item Classification Agency (GS1 Temporary Code) A classification agency or organisation whose product classification scheme is being provided to drive required information for electrical usage.
X58	ASFIS (GS1 Permanent Code) FAO alpah-3 code list for fish species identification, commercial name & scientific name.
X59	FAO fishing areas (GS1 Permanent Code) FAO fishing areas codelist.
X60	FAO Fishing gear type (GS1 Permanent Code) FAO Fishing gear type codelist.
X61	EU fish quality (GS1 Permanent Code) EU fish quality grade code list (E, A, B, C).
X62	EU fish size (GS1 Permanent Code) EU fish standardized size code list (1, 2, 3, 4, 5 & One_Size).
X63	EU fish presentation (GS1 Permanent Code) EU fish presentation code list (3 or 5 char alpha code).
ZZZ	Mutually defined Self explanatory. Note : This code value will be removed effective with directory D.04A.

1153	Reference code qualifier Code qualifying a reference.
AAB	Proforma invoice number [1088] Reference number assigned by the seller to a Proforma Invoice.
AAC	Documentary credit number [1172] Reference number assigned by issuing bank to a Documentary credit.
AAF	Debit card number A reference number identifying a debit card.
AAG	Offer or quotation number Reference number assigned by issuing party to an offer.
AAJ	Delivery order number Reference number assigned by issuer to a delivery order.

Used Codes

AAK	Despatch advice number Reference number assigned by issuing party to a despatch advice.
AAL	Drawing number Reference number identifying a specific product drawing.
AAM	Waybill number Reference number assigned to a waybill, see: 1001 = 700.
AAN	Delivery schedule number Reference number assigned by buyer to a delivery schedule.
AAO	Consignee's shipment reference number [1362] Reference assigned by the consignee to a shipment.
AAQ	Unit load device (e.g. container) identification number [8260] Marks (letters and/or numbers) which identify a unit load device e.g. freight container.
AAS	Transport document number [1188] Reference assigned by the carrier or his agent to the transport document.
AAT	Master label number Identifies the master label number of any package type.
AAU	Despatch note number [1128] Reference number assigned by the seller to a Despatch Note.
ABD	Customs tariff number (7357) Code number of the goods in accordance with the tariff nomenclature system of classification in use where the Customs declaration is made.
ABE	Declarant's reference number Unique reference number assigned to a document or a message by the declarant for identification purposes.
ABO	Originator's reference A unique reference assigned by the originator.
ABP	Declarant's Customs identity number Reference to the party whose posted bond or security is being declared in order to accept responsibility for a goods declaration and the applicable duties and taxes.
ABQ	Importer reference number Reference number assigned by the importer to identify a particular shipment for his own purposes.
ABT	Customs declaration number [1426] Number, assigned or accepted by Customs, to identify a Goods declaration.

Used Codes

ACD	**Additional reference number** Reference number provided in addition to another given reference.
ACE	**Related document number** Reference number identifying a related document.
ACK	**Bank reference** Cross reference issued by financial institution.
ACL	**Principal reference number** A number that identifies the principal reference.
ACW	**Reference number to previous message** Reference number assigned to the message which was previously issued (e.g. in the case of a cancellation, the primary reference of the message to be cancelled will be quoted in this element).
ACX	**Banker's acceptance** Reference number for banker's acceptance issued by the accepting financial institution.
ADB	**Matured certificate of deposit** Reference number for certificate of deposit allocated by issuing financial institution.
ADC	**Loan** Reference number for loan allocated by lending financial institution.
ADD	**Analysis number/test number** Number given to a specific analysis or test operation.
ADE	**Account number** Identification number of an account.
AE	**Authorization for expense (AFE) number** A number that identifies an authorization for expense (AFE). GS1 Description: A number providing authorization for a party to incur an expense.
AEK	**Payment order number** A number that identifies a payment order.
AER	**Project specification number** Reference number identifying a project specification.
AES	**Primary reference** A number that identifies the primary reference.
AFO	**Beneficiary's reference** Reference of the beneficiary.
AFS	**Beneficiary's bank reference** Reference number of the beneficiary's bank.

Used Codes

AGA	Agreement to pay number A number that identifies an agreement to pay. GS1 Description: A reference number guaranteeing a payment.
AGB	Contract party reference number Reference number assigned to a party for a particular contract.
AGG	Dispute number Reference number to a dispute notice. GS1 Description: A reference number identifying a previoulsy transmitted commercial dispute.
AGT	Service group identification number Identification used for a group of services.
AGW	Scheme/plan number Reference number assigned to a service scheme or plan.
AHJ	Payee's reference number Reference number of the party to be paid.
AHL	Creditor's reference number Reference number of the party to whom a debt is owed.
AHM	Debtor's reference number Reference number of the party who owes an amount of money.
AHU	Request for quote number Reference number assigned by the requestor to a request for quote.
AID	Certificate of conformity Certificate certifying the conformity to predefined definitions.
AIJ	Customer's individual transaction reference number Customer's reference number allocated by the customer to one specific transaction.
AIK	Bank's individual transaction reference number Bank's reference number allocated by the bank to one specific transaction.
AIZ	Consolidated invoice number Invoice number into which other invoices are consolidated.
AJS	Agreement number A number specifying an agreement between parties.
AJT	Standard Industry Classification (SIC) number A number specifying a standard industry classification.
AKJ	Direct debit reference Reference number assigned to the direct debit operation.

Used Codes

AKM	Replenishment purchase order range start number
	Starting number of a range of purchase order numbers assigned by the buyer to vendor's replenishment orders.
AKO	Action authorization number
	A reference number authorizing an action.
ALK	Consignee's invoice number
	The invoice number assigned by a consignee.
ALL	Message batch number
	A number identifying a batch of messages.
ALM	Previous delivery schedule number
	A reference number identifying a previous delivery schedule.
ALN	Physical inventory recount reference number
	A reference to a re-count of physically held inventory.
ALO	Receiving advice number
	A reference number to a receiving advice.
ALP	Returnable container reference number
	A reference number identifying a returnable container.
ALQ	Returns notice number
	A reference number to a returns notice.
ALR	Sales forecast number
	A reference number identifying a sales forecast.
ALS	Sales report number
	A reference number identifying a sales report.
ALT	Previous tax control number
	A reference number identifying a previous tax control number.
	GS1 Description: A reference number identifying a previous Tax Control (TAXCON) message number.
ALV	Registered capital reference
	Registered capital reference of a company.
AML	Replenishment purchase order range end number
	Ending number of a range of purchase order numbers assigned by the buyer to vendor's replenishment orders.
AMT	Goods and Services Tax identification number
	An identification number assigned to an organization collecting Goods and Services Taxes (GST).
ANJ	Authorization number
	A number which uniquely identifies an authorization.

Used Codes

ANL	Deposit reference number A reference number identifying a deposit. GS1 Description: A reference number identifying a physical deposit made to a financial account by a party through the bank branch network.
ANX	Clearing reference Reference allocated by a clearing procedure.
ANZ	Direct debit reference Reference of the direct debit. Notes: This code value will be removed effective with directory D.02A.
AOA	Documentary payment reference Reference of the documentary payment.
AP	Accounts receivable number Reference number assigned by accounts receivable department to the account of a specific debtor.
APF	Price/sales catalogue response reference number A reference number identifying a response to a price/sales catalogue.
APG	General purpose message reference number A reference number identifying a general purpose message. EDIFACT
APH	Invoicing data sheet reference number A reference number identifying an invoicing data sheet.
API	Inventory report reference number A reference number identifying an inventory report.
APQ	Commercial account summary reference number A reference number identifying a commercial account summary.
AQQ	Activite Principale Exercee (APE) identifier The French industry code for the main activity of a company.
AQS	Nomenclature Activity Classification Economy (NACE) identifier A European industry classification code used to identify the activity of a company.
ARZ	Stock adjustment number A number identifying a stock adjustment.
ASE	Duty free products security number A security number allocated for duty free products.
ASF	Duty free products receipt authorisation number Authorisation number allocated for the receipt of duty free products.

Used Codes

ASG	Party information message reference Reference identifying a party information message.
ASI	Proof of delivery reference number A reference number identifying a proof of delivery which is generated by the goods recipient.
ASJ	Supplier's credit claim reference number A reference number identifying a supplier's credit claim.
ASK	Picture of actual product Reference identifying the picture of an actual product.
ASL	Picture of a generic product Reference identifying a picture of a generic product.
ASO	Password Code used for authentication purposes.
ASV	Product data file number The number of a product data file.
ATB	Purchase for export Customs agreement number A number assigned by a Customs authority allowing the purchase of goods free of tax because they are to be exported immediately after the purchase. EDIFACT
AUB	Party reference The reference to a party
AUD	Collection reference A reference identifying a collection.
AUG	Importer's letter of credit reference Letter of credit reference issued by importer.
AUJ	Proposed purchase order reference number A reference number assigned to a proposed purchase order.
AUK	Application for financial support reference number Reference number assigned to an application for financial support.
AUL	Manufacturing quality agreement number Reference number of a manufacturing quality agreement.
AUQ	Customs binding ruling number Binding ruling number issued by customs.
AUR	Customs non-binding ruling number Non-binding ruling number issued by customs.
AUY	International Standard Industrial Classification (ISIC) code A code specifying an international standard industrial classification.

Used Codes

AUZ	**Customs pre-approval ruling number** Pre-approval ruling number issued by Customs.
AVB	**Product characteristics directory** A reference to a product characteristics directory. EDIFACT
AVD	**Inventory report request number** A reference to a product characteristics directory. EDIFACT
AVG	**Slaughterhouse approval number** Veterinary licence number allocated by a national authority to a Slaughterhouse. EDIFACT
AVH	**Meat cutting plant approval number** Veterinary licence number allocated by a national authority to a meat cutting plant. EDIFACT
AVQ	**Place of packing approval number** Approval Number of the place where goods are packaged. Approval number of the place where goods are packaged. In the meat sector, some additional information is required for traceability purposes: cutting party, slaugtherhouse, ...
AVS	**Mandate Reference** Reference to a specific mandate given by the relevant party for underlying business or action.
AWB	**Air waybill number** Reference number assigned to an air waybill, see: 1001 = 740.
AWS	**Hygienic Certificate number, national** Nationally set Hygienic Certificate number, such as sanitary, epidemiologic.
AWT	**Administrative Reference Code** Reference number assigned by Customs to a 'shipment of excise goods'.
AWV	**Phone number** A sequence of digits used to call from one telephone line to another in a public telephone network.
AWW	**Buyer's fund number** A reference number indicating the fund number used by the buyer. GS1 Note: Replaces GS1 Temporary Code BFN.
AWX	**Company trading account number** A reference number identifying a company trading account. GS1 Note: Replaces GS1 Temporary Code CAN.

Used Codes

AWY	Reserve goods identifier
	A reference number identifying goods in stock which have been reserved for a party.
	GS1 Note: Replaces GS1 Temporary Code GRN.
AWZ	Handling and movement reference number
	A reference number identifying a previously transmitted cargo/goods handling and movement message.
	GS1 Note: Replaces GS1 Temporary Code HN.
AXA	Instruction to despatch reference number
	A reference number identifying a previously transmitted instruction to despatch message.
	GS1 Note: Replaces GS1 Temporary Code IDR.
AXB	Instruction for returns number
	A reference number identifying a previously communicated instruction for return message.
	GS1 Note: Replaces GS1 Temporary Code IRN.
AXC	Metered services consumption report number
	A reference number identifying a previously communicated metered services consumption report.
	GS1 Note: Replaces GS1 Temporary Code MSC.
AXD	Order status enquiry number
	A reference number to a previously sent order status enquiry.
	GS1 Note: Replaces GS1 Temporary Code OSC.
AXE	Firm booking reference number
	A reference number identifying a previous firm booking.
	GS1 Note: Replaces GS1 Temporary Code PFB.
AXF	Product inquiry number
	A reference number identifying a previously communicated product inquiry.
	GS1 Note: Replaces GS1 Temporary Code PIE.
AXG	Split delivery number
	A reference number identifying a split delivery.
	GS1 Note: Replaces GS1 Temporary Code SDR.
AXH	Service relation number
	A reference number identifying the relationship between a service provider and a service client, e.g., treatment of a patient in a hospital, usage by a member of a library facility, etc.
	GS1 Note: Replaces GS1 Temporary Code SNR.
AXI	Serial shipping container code
	Reference number identifying a logisitc unit.
	GS1 Note: Replaces GS1 Temporary Code SSC.
AXJ	Test specification number
	A reference number identifying a test specification.
	GS1 Note: Replaces GS1 Temporary Code TS.

Used Codes

AXK	Transport status report number
	[1125] A reference number identifying a transport status report. GS1 Note: Replaces GS1 Temporary Code TSE.
AXL	Tooling contract number
	A reference number of the tooling contract. GS1 Note: Replaces GS1 Temporary Code XB5.
AXM	Formula reference number
	A reference number of a formula. GS1 Note: Replaces GS1 Temporary Code XB6.
AXN	Pre-agreement number
	A reference number identifying a pre-agreement. GS1 Note: Replaces GS1 Temporary Code XB7.
AXO	Product certification number
	Number assigned by a governing body (or their agents) to a product which certifies compliance with a standard. GS1 Note: Replaces GS1 Temporary Code XC1.
AXP	Consignment contract number
	Reference number identifying a consignment contract. GS1 Note: Replaces GS1 Temporary Code XC3.
AXQ	Product specification reference number
	Number assigned by the issuer to his product specification. GS1 Note: Replaces GS1 Temporary Code YA1.
AXR	Payroll deduction advice reference
	A reference number identifying a payroll deduction advice. GS1 Note: Replaces GS1 Temporary Code YA9.
BC	Buyer's contract number
	Reference number assigned by buyer to a contract.
BFN	Buyer's fund number (GS1 Temporary Code)
	A reference number indicating the fund number used by the buyer. GS1 Note: Code marked for deletion. Use value AWW instead.
BM	Bill of lading number
	Reference number assigned to a bill of lading, see: 1001 = 705.
BN	Booking reference number
	[1016] Reference number assigned by the carrier or his agent when cargo space is reserved prior to loading.
BO	Blanket order number
	Reference number assigned by the order issuer to a blanket order.
BT	Batch number/lot number
	Reference number assigned by manufacturer to a series of similar products or goods produced under similar conditions.

Used Codes

CAN	Company trading account number (GS1 Temporary Code)
	A reference number identifying a company trading account.
	GS1 Note: Code marked for deletion. Use value AWX instead.
CBB	Order shipment grouping reference
	A reference number identifying the grouping of purchase orders into one shipment.
	GS1 Note: Replaces GS1 Temporary Code YB4.
CD	Credit note number
	Reference number assigned to a credit note.
CED	Debit Letter number
	Reference number identifying the letter of debit document.
	GS1 Note: Replaces GS1 Temporary Code YB8.
CFF	Animal farm licence number
	Veterinary licence number allocated by a national authority to an animal farm.
	GS1 Note: Replaces GS1 Temporary Code YC3.
CH	Customer catalogue number
	Number identifying a catalogue for customer's usage.
CK	Cheque number
	Unique number assigned to one specific cheque.
CMR	Road consignment note number
	Reference number assigned to a road consignment note, see: 1001 = 730.
CN	Carrier's reference number
	Reference number assigned by carrier to a consignment.
CNE	Consolidated reference number (GS1 Temporary Code)
	A number identifying a consolidated reference.
CO	Buyers order number
	[1022] Reference number assigned by the buyer to an order.
COF	Call off order number
	A number that identifies a call off order.
CR	Customer reference number
	Reference number assigned by the customer to a transaction.
CT	Contract number
	Reference number of a contract concluded between parties.
CU	Consignor's reference number
	[1140] Reference number assigned by a consignor to a particular shipment for his own purposes or for those of the consignee.
CZ	Cooperation contract number
	Number issued by a party concerned given to a contract on cooperation of two or more parties.

Used Codes

DDC	Direct debit contract reference (SWIFT Code) A reference number identifying a direct debit contract.
DL	Debit note number Reference number assigned by issuer to a debit note.
DM	Document number [1004] Reference number assigned to the document by the issuer.
DQ	Delivery note number Reference number assigned by the issuer to a delivery note.
ECN	External consolidation reference number (GS1 Temporary Code) A reference number assigned to identify an external consolidation.
EID	Economic operator identifier (EO-ID) (GS1 Temporary Code) Specify the economic operator identifier (EO-ID) number, e.g. in tobacco traceability.
ERC	External recap reference number (GS1 Temporary Code) A reference number identifying an external recap.
EX	Export licence number [1208] Reference number assigned by issuing authority to an Export Licence.
FC	Fiscal number Tax payer's number. Number assigned to individual persons as well as to corporates by a public institution; this number is different from the VAT registration number.
FF	Freight forwarder's reference number [1460] Reference number assigned to the consignment by the freight forwarder.
FI	File line identifier Number assigned by the file issuer or sender to identify a specific line.
FID	Facility identifier (F-ID) (GS1 Temporary Code) Identifies the place, for example the POS or warehouse where tobacco products are traded.
FV	File version number Number given to a version of an identified file.
FX	Foreign exchange contract number Reference number identifying a foreign exchange contract.
GC	Government contract number Number assigned to a specific government/public contract.

Used Codes

GN	Government reference number
	A number that identifies a government reference.
	GS1 Description:
	This code value should not be used to provide the tax identification number for a party (use code VA).
GRN	Goods reserve number (GS1 Temporary Code)
	A reference number identifying goods in stock which have been reserved for a party.
	GS1 Note: Code marked for deletion. Use value AWY instead.
HN	Handling and movement reference number (GS1 Temporary Code)
	A reference number identifying a previously transmitted cargo/goods handling and movement message.
	GS1 Note: Code marked for deletion. Use value AWZ instead.
HS	Harmonised system number
	Number specifying the goods classification under the Harmonised Commodity Description and Coding System of the Customs Co-operation Council (CCC).
HWB	House waybill number
	Reference number assigned to a house waybill, see: 1001 = 703.
IA	Internal vendor number
	Number identifying the company-internal vending department/unit.
IDR	Instruction to despatch reference number (GS1 Temporary Code)
	A reference number identifying a previously transmitted instruction to despatch message.
	GS1 Note: Code marked for deletion. Use value AXA instead.
IP	Import licence number
	[1106] Reference number assigned by the issuing authority to an Import Licence.
IRN	Instruction for returns number (GS1 Temporary Code)
	A reference number identifying a previously communicated instruction for return message.
	GS1 Note: Code marked for deletion. Use value AXB instead.
IT	Internal customer number
	Number assigned by a seller, supplier etc. to identify a customer within his enterprise.
IV	Invoice number
	[1334] Reference number assigned by the seller to a Commercial Invoice.
LC	Letter of credit number
	Reference number identifying the letter of credit document.
LI	Line item reference number
	(1156) Reference number identifying a particular line in a document.

Used Codes

MB	Master bill of lading number Reference number assigned to a master bill of lading, see: 1001 = 704.
MF	Manufacturer's part number Reference number assigned by the manufacturer to his product or part.
MG	Meter unit number Number identifying a unique meter unit.
MH	Manufacturing order number Reference number assigned by manufacturer for a given production quantity of products.
MR	Message recipient A number that identifies the message recipient. GS1 Description: Party who receives the message.
MS	Message sender A number that identifies the message sender. GS1 Description: Party who sends the message.
MSC	Metered services consumption report (GS1 Temporary Code) A reference number identifying a previously communicated metered services consumption report. GS1 Note: Code marked for deletion. Use value AXC instead.
MSS	Manufacturer's material safety data sheet number A number that identifies a manufacturer's material safety data sheet.
MWB	Master air waybill number Reference number assigned to a master air waybill, see: 1001 = 741.
ON	Order number (buyer) [1022] Reference number assigned by the buyer to an order.
OSE	Order status enquiry (GS1 Temporary Code) A reference number to a previously sent order status enquiry. GS1 Note: Code marked for deletion. Use value AXD instead.
PB	Payer's financial institution account number Originated company account number (ACH transfer), check, draft or wire.
PD	Promotion deal number Number assigned by a vendor to a special promotion activity.
PFB	Firm booking reference number (GS1 Temporary Code) A reference number identifying a previous firm booking. GS1 Note: Code marked for deletion. Use value AXE instead.

Used Codes

PIE	Product inquiry number (GS1 Temporary Code) A referenece number identifying a previously communicated product inquiry number. GS1 Note: Code marked for deletion. Use value AXF instead.
PK	Packing list number (1014) Reference number assigned to a packing list, see: 1001 = 271.
PL	Price list number Reference number assigned to a price list. GS1 Description: This code should be used to identify a Price/Sales Catalogue (PRICAT) message.
POR	Purchase order response number Reference number assigned by the seller to an order response.
PP	Purchase order change number Reference number assigned by a buyer for a revision of a purchase order.
PQ	Payment reference Reference number assigned to a payment.
PR	Price quote number Reference number assigned by the seller to a quote.
PW	Prior purchase order number Reference number of a purchase order previously sent to the supplier.
PY	Payee's financial institution account number Receiving company account number (ACH transfer), check, draft or wire.
RA	Remittance advice number A number that identifies a remittance advice.
RAK	Rack identification (GS1 Temporary Code) Identification of a warehouse rack in the location for shipment pick-up.
RCE	Recap number (GS1 Temporary Code) A reference number identifying a recap.
RCN	Railway consignment note number Reference number assigned to a rail consignment note, see: 1001 = 720.
RF	Export reference number Reference number given to an export shipment.
SB	Sales region number A number that identifies a sales region.
SD	Sales department number A number that identifies a sales department.

Used Codes

SDR	Split delivery reference number (GS1 Temporary Code) A reference number identifying a split delivery. GS1 Note: Code marked for deletion. Use value AXG instead.
SE	Serial number Identification number of an item which distinguishes this specific item out of an number of identical items.
SN	Seal number [9308] Identification number on Customs or other seals affixed to containers or other transport units.
SNR	Service relation number (GS1 Temporary Code) A number used to identify a database entry which records recurring services, e.g., treatment of a patient in a hospital, usage by a member of a library facility, etc. GS1 Note: Code marked for deletion. Use value AXH instead.
SRN	Shipment reference number Reference number assigned to a shipment. GS1 Description: Reference number assigned by a consignor to a particular shipment for his own purposes or for those of the consignee.
SS	Seller's reference number Reference number assigned to a transaction by the seller.
SSC	Serial shipping container code (GS1 Temporary Code) Reference number identifying a serial shipping container or package. GS1 Note: Code marked for deletion. Use value AXI instead.
SZ	Specification number Number assigned by the issuer to his specification.
TAU	Aggregated level unique identifier (aUI) (GS1 Temporary Code) Reference the aggregated level unique identifier (aUI), e.g. in tobacco traceability.
TIN	Transport instruction number A reference number identifying a transport instruction. EDIFACT
TL	Tax exemption licence number Number assigned by the tax authorities to a party indicating its tax exemption authorization. This number could relate to a specified business type, a specified local area or a class of products.
TP	Test report number Reference number identifying a test report document relevant to the product.
TRB	Tribunal place registration number (GS1 Temporary Code) Registration number of a company at the tribunal place.

Used Codes

TS	Test specification number (GS1 Temporary Code)
	A reference number identifying a test specification.
	GS1 Note: Code marked for deletion. Use value AXJ instead.
TSE	Transport status number (GS1 Temporary Code)
	A reference number identifying a transport status message.
	GS1 Note: Code marked for deletion. Use value AXK instead.
TUU	Aggregated level unique identifier (upUI) (GS1 Temporary Code)
	Identifies the single pack of cigarettes issued by a central EU repository.
UC	Ultimate customer's reference number
	The originator's reference number as forwarded in a sequence of parties involved.
UCN	Unique consignment reference number
	(1202) Unique reference of a consignment (UCRN) used for identification purposes in documents and messages exchanged between parties in international trade. See also: Unique Identifier Code (UNIC) in UN/ECE Recommendation No. 8, March 1992.
UO	Ultimate customer's order number
	The originator's order number as forwarded in a sequence of parties involved.
VA	VAT registration number
	Unique number assigned by the relevant tax authority to identify a party for use in relation to Value Added Tax (VAT).
VN	Order number (supplier)
	Reference number assigned by supplier to a buyer's purchase order.
XA	Company/place registration number
	Company registration and place as legally required.
XA4	Account servicing bank reference (SWIFT Code)
	A reference number allocated by an account servicing bank.
XA5	Customer to customer reference number (SWIFT Code)
	A reference number exchanged between customers.
XA6	Third party reference number (SWIFT Code)
	A number used to identify references related to third parties.
XA8	Credit card number (SWIFT Code)
	A reference number identifying a credit card.
XB1	Clearing number (SWIFT Code)
	A reference number identifying a clearing.
XB5	Tooling contract number (GS1 Temporary Code)
	Number of the tooling contract.
	GS1 Note: Code marked for deletion. Use value AXL instead.

Used Codes

XB6	Formula number (GS1 Temporary Code)
	Number of the formula. GS1 Note: Code marked for deletion. Use value AXM instead.
XB7	Pre-agreement number (GS1 Temporary Code)
	Number identifying a pre-agreement. GS1 Note: Code marked for deletion. Use value AXN instead.
XC1	Product certification number (GS1 Temporary Code)
	Number assigned by a governing body (or their agents) to a product which certifies compliance with a standard. GS1 Note: Code marked for deletion. Use value AXO instead.
XC3	Consignment contract number (GS1 Temporary Code)
	Reference number identifying a consignment contract. GS1 Note: Code marked for deletion. Use value AXP instead.
YA1	Product specification reference number (GS1 Temporary Code)
	Number assigned by the issuer to his product specification. GS1 Note: Code marked for deletion. Use value AXQ instead.
YA3	Numbering per year (GS1 Temporary Code)
	Financial statement should be identified consecutively numbered per year.
YA6	Bank statement number (SWIFT Code)
	A reference number identifying a bank statement.
YA9	Payroll deduction advice reference (GS1 Temporary Code)
	A reference number identifying a payroll deduction advice. GS1 Note: Code marked for deletion. Use value AXR instead.
YB4	Order shipment grouping reference (GS1 Temporary Code)
	A reference number identifying the grouping of purchase orders into one shipment. GS1 Note: Code marked for deletion. Use value CBB instead.
YB8	Debit Letter (GS1 Temporary Code)
	Reference number identifying the letter of debit document. GS1 Note: Code marked for deletion. Use value CED instead.
YC1	Additional party identification (GS1 Temporary Code)
	Reference number to an additional party identification. This number may be the internal trading partner identification number used by a party to identify its trading parties.
YC3	Farm approval number (GS1 Temporary Code)
	Veterinary licence number allocated by a national authority to an animal farm.
YC6	Electrical and Electronic Equipment Producer registration number (GS1 Temporary Code)
	National registration number of the producers of Electrical and Electronic Equipment

Used Codes

YC7	Batteries and Accumulators Producer registration number (GS1 Temporary Code)
	National registration number of the producers of Batteries and Accumulators
ZZZ	Mutually defined reference number
	Number based on party agreement.

1225	Message function code
	Code indicating the function of the message.
9	Original
	Initial transmission related to a given transaction.

2005	Date or time or period function code qualifier
	Code qualifying the function of a date, time or period.
137	Document/message date/time
	(2006) Date/time when a document/message is issued. This may include authentication.
171	Reference date/time
	Date/time on which the reference was issued.

2379	Date or time or period format code
	Code specifying the representation of a date, time or period.
2	DDMMYY
	Calendar date: D = Day; M = Month; Y = Year.
101	YYMMDD
	Calendar date: Y = Year; M = Month; D = Day.
102	CCYYMMDD
	Calendar date: C = Century ; Y = Year ; M = Month ; D = Day.
104	MMWW-MMWW
	A period of time specified by giving the start week of a month followed by the end week of a month. Data is to be transmitted as consecutive characters without hyphen.
107	DDD
	Day's number within a specific year: D = Day.
108	WW
	Week's number within a specific year: W = Week.
109	MM
	Month's number within a specific year: M = Month.
110	DD
	Day's number within is a specific month.

Used Codes

201	YYMMDDHHMM	
	Calendar date including time without seconds: Y = Year; M = Month; D = Day; H = Hour; M = Minute.	
203	CCYYMMDDHHMM	
	Calendar date including time with minutes: C=Century; Y=Year; M=Month; D=Day; H=Hour; M=Minutes.	
204	CCYYMMDDHHMMSS	
	Calendar date including time with seconds: C=Century;Y=Year; M=Month; D=Day;H=Hour;M=Minute;S=Second.	
401	HHMM	
	Time without seconds: H = Hour; m = Minute.	
501	HHMMHHMM	
	Time span without seconds: H = Hour; m = Minute;.	
502	HHMMSS-HHMMSS	
	Format of period to be given without hyphen.	
602	CCYY	
	Calendar year including century: C = Century; Y = Year.	
609	YYMM	
	Month within a calendar year: Y = Year; M = Month.	
610	CCYYMM	
	Month within a calendar year: CC = Century; Y = Year; M = Month.	
615	YYWW	
	Week within a calendar year: Y = Year; W = Week 1st week of January = week 01.	
616	CCYYWW	
	Week within a calendar year: CC = Century; Y = Year; W = Week (1st week of January = week 01).	
713	YYMMDDHHMM-YYMMDDHHMM	
	Format of period to be given in actual message without hyphen.	
715	YYWW-YYWW	
	A period of time specified by giving the start week of a year followed by the end week of year (both not including century). Data is to be transmitted as consecutive characters without hyphen.	
717	YYMMDD-YYMMDD	
	Format of period to be given in actual message without hyphen.	
718	CCYYMMDD-CCYYMMDD	
	Format of period to be given without hyphen.	

Used Codes

719	CCYYMMDDHHMM-CCYYMMDDHHMM	A period of time which includes the century, year, month, day, hour and minute. Format of period to be given in actual message without hyphen.
720	DHHMM-DHHMM	Format of period to be given without hyphen (D=day of the week, 1=Monday; 2=Tuesday; ... 7=Sunday).
801	Year	To indicate a quantity of years.
802	Month	To indicate a quantity of months.
803	Week	To indicate a quantity of weeks.
804	Day	To indicate a quantity of days.
805	Hour	To indicate a quantity of hours.
806	Minute	To indicate a quantity of minutes.
810	Trimester	To indicate a quantity of trimesters (three months).
811	Half month	To indicate a quantity of half months.
21E	DDHHMM-DDHHMM (GS1 Temporary Code)	Format of period to be given in actual message without hyphen.

3035	Party function code qualifier	Code giving specific meaning to a party.
AB	Buyer's agent/representative	Third party who arranged the purchase of merchandise on behalf of the actual buyer.
ACD	Party has access to all non publicly available data (GS1 Temporary Code)	The identified party has access to all non publicly available pricing and non-pricing data associated with the current product.
ACN	Party has access only to non publicly available non-pricing data (GS1 Temporary Code)	The identified party has access only to the non publicly available non-pricing data associated with the current product.

Used Codes

ACP	Party has access only to non publicly available pricing data (GS1 Temporary Code) The identified party has access only to the non publicly available pricing data associated with the current product.
AE	Declarant's agent/representative Any natural or legal person who makes a declaration to an official body on behalf of another natural or legal person, where legally permitted (CCC).
AG	Agent/representative (3196) Party authorized to act on behalf of another party.
AP	Accepting party (3352) Party accepting goods, products, services etc.
AS	Account servicing financial institution Identifies the financial institution servicing the account(s).
BE	Beneficiary The ultimate recipient of the funds. Normally the account owner who is reimbursed by the payor.
BF	Beneficiary's bank Identifies the account servicer for the beneficiary or the payee.
BK	Financial institution Party acting as financial institution.
BL	Bill of lading recipient Party to receive B/L.
BO	Broker or sales office Party acting in the name of the seller as broker or as sales office.
BQ	Cheque drawn bank Identifies the bank on which the cheque should be drawn, as instructed by the ordering customer.
BS	Bill and ship to Party receiving goods and relevant invoice.
BY	Buyer Party to whom merchandise and/or service is sold.
CA	Carrier (3126) Party undertaking or arranging transport of goods between named points.
CG	Carrier's agent Party authorized to act for or on behalf of carrier.
CH	Connecting carrier Owner or operator of a transportation conveyance to which goods in a given transaction will be transferred.

Used Codes

CK	Empty equipment despatch party Party from whose premises empty equipment will be or has been despatched.
CM	Customs Identification of customs authority relevant to the transaction or shipment.
CN	Consignee (3132) Party to which goods are consigned.
CO	Corporate office Identification of the Head Office within a company.
COD	Quotation requesting party The party sending the requests for quotation. GS1 Note: Replaces GS1 Temporary Code QP. EDIFACT
CPE	Central payment service (GS1 Temporary Code) Master of the conveyance. GS1 Description: A party providing central (or consolidated payment) services.
CPU	Central procurement party (GS1 Temporary Code) Party responsible for all aspects (e.g. tenders, orders, invoices, ..) of procurement.
CQ	Cheque order Party to which the cheque will be ordered, when different from the beneficiary.
CR	Empty equipment return party Party to whose premises empty equipment will be or has been returned.
CRB	Creditor's bank (SWIFT Code) Identifies the account servicer for the creditor.
CRE	Creditor (SWIFT Code) The party to be credited with funds.
CS	Consolidator Party consolidating various consignments, payments etc.
CW	Equipment owner Owner of equipment (container, etc.).
CX	Consignee's agent Party authorized to act on behalf of the consignee.
CZ	Consignor (3336) Party which, by contract with a carrier, consigns or sends goods with the carrier, or has them conveyed by him. Synonym: shipper, sender.
DBB	Debtor's bank (SWIFT Code) Identifies the account servicer for the debtor.

Used Codes

DCS	**Temporary employee** A person employed on a temporary basis.
DCT	**Designer** A party who designs.
DCU	**Quotation delivered to** Party to whom the quotation is to be or has been delivered. EDIFACT
DCV	**Developer** A party who develops.
DCX	**Party to receive refund** Party to whom a refund is given.
DEF	**Meat cutter** Person whose job is to cut up and/or mince meat. EDIFACT
DEQ	**Shipper** Party responsible for the shipment of goods.
DER	**Source data pool** A data pool that supports the functionality required by a data source such as data loading, publication, notification, registration, etc.
DES	**Brand owner** The owner of a brand.
DFZ	**Article information responsible party** The party responsible for article information. GS1 Note: Replaces GS1 Temporary Code IPD.
DGA	**Price information responsible party** The party responsible for price information. GS1 Note: Replaces GS1 Temporary Code IPR.
DGB	**Invoice processing party** Party to whom the invoice is sent and who processes the invoice on behalf of the invoicee. Note, the invoicee is legally responsible for the invoice and can be different to the processing party. GS1 Note: Replaces GS1 Temporary Code ITO.
DGC	**Logistic service provider** A party providing logistic services for another party (e.g re-packing suppliers products) on products. GS1 Note: Replaces GS1 Temporary Code LSP.
DGD	**Fattener** Party which provides fattening services. GS1 Note: Replaces GS1 Temporary Code X51.

Used Codes

DGE	Breeder	Party which provides breeding. GS1 Note: Replaces GS1 Temporary Code X52.
DL	Factor	Company offering a financial service whereby a firm sells or transfers title to its accounts receivable to the factoring company.
DM	Party to whom documents are to be presented	Party to whom documents are to be presented.
DP	Delivery party	(3144) Party to which goods should be delivered, if not identical with consignee. GS1 Description: Party to which goods should be delivered, if not the same as the buyer.
DS	Distributor	Party distributing goods, financial payments or documents.
EM	Party to receive electronic memo of invoice	Party being informed about invoice issue (via EDI).
EO	Owner of equipment	Party who owns equipment.
EX	Exporter	(3030) Party who makes - or on whose behalf a Customs clearing agent or other authorized person makes - an export declaration. This may include a manufacturer, seller or other person. Within a Customs union, consignor may have the same meaning as exporter.
FD	Buyer's parent company	Parent company, e.g. holding company.
FP	Freight/charges payer	Party responsible for the payment of freight.
FR	Message from	Party where the message comes from.
FW	Freight forwarder	Party arranging forwarding of goods.
GL	Socially insured person	A person who is registered in a social security scheme.
GM	Inventory controller	To specifically identify the party in charge of inventory control.
GO	Goods owner	The party which owns the goods.

Used Codes

GQ	**Slaughterer**	
	Party or person who has undertaken or will undertake a slaughter.	
GW	**Party fulfilling all operations**	
	Code indicating the fact that the party identified carries out all operations within that company's activities.	
GX	**Central catalogue party**	
	Party controlling a central catalogue.	
GY	**Inventory reporting party**	
	Party reporting inventory information.	
GZ	**Substitute supplier**	
	Party which may be in a position to supply products or services should the main usual supplier be unable to do so.	
HP	**Final message recipient**	
	To identify the final recipient of the message.	
HQ	**Owner of account (SWIFT Code)**	
	Identifies the owner of the account.	
HX	**Debtor (SWIFT Code)**	
	Party from whom payment is due.	
I1	**Intermediary bank 1**	
	A financial institution between the ordered bank and the beneficiary's bank.	
I2	**Intermediary bank 2**	
	A financial institution between the ordered bank and the beneficiary's bank.	
II	**Issuer of invoice**	
	(3028) Party issuing an invoice.	
IM	**Importer**	
	(3020) Party who makes - or on whose behalf a Customs clearing agent or other authorized person makes - an import declaration. This may include a person who has possession of the goods or to whom the goods are consigned.	
IN	**Insurer**	
	A person or company offering insurance policies for premiums.	
IPA	**Party information party (GS1 Temporary Code)**	
	The party in a company who is responsible for the party information. The PARTIN message may be requested from or sent by this party.	
IPD	**Article information party (GS1 Temporary Code)**	
	The party in a company who is responsible for the pricing or other article information. The PRICAT or PRODAT messages may be requested from or sent by this party. GS1 Note: Code marked for deletion. Use value DFZ instead.	

Used Codes

IPR	Price information party (GS1 Temporary Code)
	The party in a company who is responsible for the price information. The PRICAT message may be requested from or sent by this party. GS1 Note: Code marked for deletion. Use value DGA instead.
ITO	Invoice recipient party (GS1 Temporary Code)
	Party to whom the invoice is sent and who processes the invoice on behalf of the invoicee. Note, the invoicee is legally responsible for the invoice and can be different to the processing party. GS1 Note: Code marked for deletion. Use value DGB instead.
IV	Invoicee
	(3006) Party to whom an invoice is issued.
JB	Goods collection party
	Party that will collect or has collected the goods.
	GS1 Description: Party that will collect or has collected the goods.
LC	Party declaring the Value Added Tax (VAT)
	A code to identify the party who is responsible for declaring the Value Added Tax (VAT) on the sale of goods or services.
LD	Party recovering the Value Added Tax (VAT)
	A code to identify the party who is eligible to recover the Value Added Tax (VAT) on the sale of goods or services.
LF	Buyer's corporate office
	The identification of the buyer's corporate office.
LG	Supplier's corporate office
	The identification of the supplier's corporate office.
LP	Loading party
	Party responsible for the loading when other than carrier.
LSP	Logistic Service Provider (GS1 Temporary Code)
	A party providing logistic services for another party (e.g re-packing suppliers products) on products which may lead to added value for the product. GS1 Note: Code marked for deletion. Use value DGC instead.
MA	Party for whom item is ultimately intended
	Party for whom item is ultimately intended.
MF	Manufacturer of goods
	Party who manufactures the goods.
MP	Manufacturing plant
	Self explanatory.
	GS1 Description: Industrial department of a company in which goods are manufactured with appropriate equipment and fittings.

Used Codes

MR	Message recipient	A party to receive a message or messages.
MS	Document/message issuer/sender	Issuer of a document and/or sender of a message.
N1	Notify party no. 1	The first party which is to be notified.
N2	Notify party no. 2	The second party which is to be notified.
NFP	No function priority allocated (GS1 Temporary Code)	Code indicating that the party identified is capable of carrying out all or most functions within the party.
NI	Notify party	(3180) Party to be notified of arrival of goods.
OB	Ordered by	Party who issued an order. GS1 Description: Party who issued an order for goods and services.
OR	Ordered bank	Identifies the account servicer for the ordering customer or payor.
OS	Original shipper	The original supplier of the goods.
OV	Owner of means of transport	(3126) Party owning the means of transport. No synonym of carrier = CA.
OY	Ordering customer	Identifies the originator of the instruction. GS1 Description: Only used in financial messages.
P1	Contact party 1	First party to contact.
P2	Contact party 2	Second party to contact.
PB	Paying financial institution	Financial institution designated to make payment.
PE	Payee	Identifies the credit party when other than the beneficiary.
PF	Party to receive freight bill	Party to whom the freight bill should be sent.

Used Codes

PL	Payor	Identifies the debit party when other than the ordering customer (for banking purposes).
PO	Ordering party	To be used only if ordering party and buyer are not identical.
PR	Payer	(3308) Party initiating payment.
PW	Despatch party	(3282) Party where goods are collected or taken over by the carrier (i.e. if other than consignor).
PX	Party to receive all documents	A party which is named to be the recipient of all documents.
PY	Checking party	Party or contact designated on behalf of carrier or his agent to establish the actual figures for quantities, weight, volume and/or (cube) measurements of goods or containers which are to appear in the transport contract and on which charges will be based.
RA	Central bank or regulatory authority	Identifies central bank or regulatory authority which must be informed of certain aspects of a message.
RB	Receiving financial institution	Financial institution designated to receive payment.
RE	Party to receive commercial invoice remittance	Party to whom payment for a commercial invoice or bill should be remitted.
RH	Seller's financial institution	Financial institution designated by seller to receive payment. RDFI (ACH transfers).
RV	Receiver of cheque	Identifies the party which is to receive the actual cheque, when different from the receiver of funds.
SA	Sales person number (GS1 Temporary Code)	The identification of a sales person number. GS1 Note: Code marked for deletion. Use value SE instead.
SE	Seller	(3346) Party selling merchandise to a buyer. GS1 Note: Replaces GS1 Temporary Code SA.
SF	Ship from	Identification of the party from where goods will be or have been shipped.

Used Codes

SN	**Store number**
	A party keeping a shop or store.
	GS1 Description:
	Number allocated to identify a store.
SR	**Supplier's agent/representative**
	(3254) Party representing the seller for the purpose of the trade transaction.
	GS1 Description:
	Party representing the supplier for the purpose of the trade transaction.
SS	**Social securities collector's office**
	Party collecting social securities premiums.
ST	**Ship to**
	Identification of the party to where goods will be or have been shipped.
SU	**Supplier**
	Party who supplies goods and/or services.
	GS1 Description:
	Party which provides service(s) and/or manufactures or otherwise has possession of goods, and consigns or makes them available in trade.
TC	**Tax collector's office**
	Party collecting taxes.
TPE	**Testing party (GS1 Temporary Code)**
	A party authorized to carry out a specified test.
TS	**Party to receive certified test results**
	Party to whom the certified test results should be sent.
UC	**Ultimate consignee**
	Party who has been designated on the invoice or packing list as the final recipient of the stated merchandise.
UD	**Ultimate customer**
	The final recipient of goods.
WH	**Warehouse keeper**
	(3022) Party taking responsibility for goods entered into a warehouse.
WS	**Wholesaler**
	Seller of articles, often in large quantities, to be retailed by others.
X47	**Cash register number (GS1 Temporary Code)**
	Number allocated to identify a cash register.
X48	**Corporate identity (GS1 Temporary Code)**
	The identity of party to whom all other parties of the same commercial organisation are linked.

Used Codes

X50	Mincing plant (GS1 Temporary Code)
	A place where the meat of animals is cut into very small pieces using a meat grinder.
	GS1 Note: Code marked for deletion.
X51	Fattener (GS1 Temporary Code)
	Party which fattens the animal.
	GS1 Note: Code marked for deletion. Use value DGD instead.
X52	Breeder (GS1 Temporary Code)
	Party which breeds the animal.
	GS1 Note: Code marked for deletion. Use value DGE instead.
X53	Content Owner (GS1 Temporary Code)
	Not available.
	GS1 Note: Code marked for deletion.
X54	Temperature variation (GS1 Temporary Code)
	Temperature variation upward or downward
X56	No / missing loading space (GS1 Temporary Code)
	The goods/consignment/equipment could not be loaded because of no/missing loading space.
ZZZ	Mutually defined
	Party specification mutually agreed between interchanging parties.

3045	Party name format code
	Code specifying the representation of a party name.
1	Name components in sequence as defined in description below
	Name component 1: Family name. Name component 2: Given name or initials. Name component 3: Given name or initials. Name component 4: Maiden name. Name component 5: Title Group of name components transmitted in sequence with name component 1 transmitted first. The maiden name is the family name given at birth of a female. Other names are self-explanatory.

3055	Code list responsible agency code
	Code specifying the agency responsible for a code list.
2	CEC (Commission of the European Communities)
	Generic: see also 140, 141, 142, 162.
	GS1 Description:
	Commission of the European Communities
3	IATA (International Air Transport Association)
	The airline industry's international organisation.
	GS1 Description:
	International Air Transport Association
5	ISO (International Organization for Standardization)
	International Organization of Standardization.

Used Codes

6	UN/ECE (United Nations - Economic Commission for Europe) United Nations Economic Commission for Europe.
7	CEFIC (Conseil Europeen des Federations de l'Industrie Chimique) EDI project for chemical industry.
8	EDIFICE Standardised electronic commerce forum for companies with interests in computing, electronics and telecommunications. GS1 Description: EDI Forum for companies with Interest in Computing and Electronics (EDI project for EDP/ADP sector).
9	GS1 GS1 (formerly EAN International), an organisation of GS1 Member Organisations, which manages the GS1 System. GS1 Description: GS1 International.
10	ODETTE Organization for Data Exchange through Tele-Transmission in Europe (European automotive industry project).
17	S.W.I.F.T. Society for Worldwide Interbank Financial Telecommunications s.c.
28	EDITEUR (European book sector electronic data interchange group) Code identifying the pan European user group for the book industry as an organisation responsible for code values in the book industry.
60	Assigned by national trade agency The code list is from a national agency.
65	GS1 France Organisation responsible for GS1 System in France.
68	GS1 Italy Organisation responsible for GS1 System in Italy.
83	US, National Retail Federation The National Retail Federation is the trade association for the general merchandise retailing industry. In addition to providing support and education services, they also maintain and publish standard colour and size codes for the retail industry.
84	DE, BRD (Gesetzgeber der Bundesrepublik Deutschland) German legislature.
86	Assigned by party originating the message Codes assigned by the party originating the message.
87	Assigned by carrier Codes assigned by the carrier.

Used Codes

88	Assigned by owner of operation Assigned by owner of operation (e.g. used in construction).
89	Assigned by distributor Codes assigned by a distributor.
90	Assigned by manufacturer Code assigned by the manufacturer.
91	Assigned by supplier or supplier's agent Codes assigned by a seller or seller's agent. GS1 Description: Code assigned by the supplier or supplier's agent.
92	Assigned by buyer or buyer's agent Codes assigned by a buyer or buyer's agent.
112	US, U.S. Census Bureau The Bureau of the Census of the U.S. Dept. of Commerce.
113	GS1 US Organisation responsible for GS1 System in the USA.
116	US, ANSI ASC X12 American National Standards Institute ASC X12.
131	DE, German Bankers Association German Bankers' Association.
136	GS1 UK Organisation responsible for GS1 System in the UK.
137	AT, Verband oesterreichischer Banken und Bankiers Austrian bankers association.
174	DE, DIN (Deutsches Institut fuer Normung) German standardization institute.
182	US, Standard Carrier Alpha Code (Motor) Organisation maintaining the SCAC lists and transportation operating in North America.
194	AU, AQIS (Australian Quarantine and Inspection Service) Australian Quarantine and Inspection Service.
200	GS1 Netherlands Organisation responsible for GS1 System in the Netherlands.
245	GS1 Denmark Organisation responsible for GS1 System in Denmark.

Used Codes

246	GS1 Germany Organisation responsible for GS1 System in Germany. GS1 Description: German representative of International Article Numbering association (GS1).
260	Ediel Nordic forum A code to identify Ediel Nordic forum, which is an organization standardizing the use of EDI between the participants in the Nordic power market.
281	GS1 Belgium & Luxembourg Organisation responsible for GS1 System in Belgium & Luxembourg.
286	SE, TCO (Tjänstemännes Central Organisation) The Swedish Confederation of Professional Employees.
294	GS1 Austria Organisation responsible for the GS1 System in Austria.
295	AU, Therapeutic Goods Administration Austrialian administration responsible for the regulation of therapeutic goods in Australia. EDIFACT
297	IT, Ufficio IVA Ufficio responsabile gestione partite IVA, Italy (Italian Institute issuing VAT registration numbers). EDIFACT
298	GS1 Spain Organisation responsible for the GS1 System in Spain.
316	GS1 Finland Organisation responsible for the GS1 system in Finland.
317	GS1 Brazil Organisation responsible for the GS1 system in Brazil.
324	GS1 Ireland Organisation responsible for the GS1 system in Ireland.
325	GS1 Russia Organisation responsible for the GS1 system in Russia.
326	GS1 Poland Organisation responsible for the GS1 system in Poland.
327	GS1 Estonia Organisation responsible for the GS1 system in Estonia.
376	PANTONE Color code controlling organisation
400	FAO (Food and Agriculture Organisation) Food and Agriculture Organisation of the United Nations.

Used Codes

403	Comite Europeen de Normalisation Comite Européen de Normalisation (CEN), European committee for standardisation. GS1 Note: Replaces GS1 Temporary Code CEN.
404	Assigned by logistics service provider Codes assigned by a logistics service provider. GS1 Note: Replaces GS1 Temporary Code X6.
CEN	Comite European de Normalisation (GS1 Temporary Code) Comite European de Normalisation. GS1 Note: Code marked for deletion. Use value 403 instead.
PMS	Pantone Matching System (GS1 Temporary Code) Pantone Matching System.
RAL	DE, Deutsches Institut fuer Guetesicherung und Kennzeichnung (GS1 Temporary Code) German Institute for Quality Assurance and Certification.
X5	IT, Ufficio IVA (GS1 Temporary Code) Ufficio responsabile gestione partite IVA, Italy (Italian Institute issuing VAT registration numbers).
X6	Assigned by logistics service provider (GS1 Temporary Code) Codes assigned by the logistics service provider. GS1 Note: Code marked for deletion. Use value 404 instead.
ZZZ	Mutually defined A code assigned within a code list to be used on an interim basis and as defined among trading partners until a precise code can be assigned to the code list.

3139	Contact function code Code specifying the function of a contact (e.g. department or person).
AA	Insurance contact Department/person to contact for matters regarding insurance.
AD	Accounting contact The contact responsible for accounting matters.
AE	Contract contact Department/person to contact for matters regarding contracts.
AM	Claims contact Department/person to contact for matters regarding claims.
AP	Accounts payable contact Department/person responsible for the accounts payable function within a corporation.

Used Codes

AR	Accounts receivable contact Department/person responsible for the accounts receivable within a corporation.
BC	Banking contact Contact person for bank.
BJ	Department or person responsible for processing purchase order Identification of the department or person responsible for the processing of purchase orders.
BN	Certification contact Code specifying a contact with knowledge of a certification action.
BO	After business hours contact Department/person to contact after normal working hours.
BR	Cook Person responsible for cooking. GS1 Note: Replaces GS1 Temporary Code CKE.
CB	Changed by Person who made the change.
CKE	Cook (GS1 Temporary Code) Person responsible for cooking. GS1 Note: Code marked for deletion. Use value BR instead.
CN	Consignee (3132) Party to which goods are consigned.
CO	Consignor (3336) Party which, by contract with a carrier, consigns or sends goods with the carrier, or has them conveyed by him. Synonym: shipper/sender.
CP	Responsible person for computer data processing Responsible person to contact for matters regarding computer data processing.
CR	Customer relations Individual responsible for customer relations.
DE	Department/employee to execute export procedures Department/employee which/who executes export procedures.
DI	Department/employee to execute import procedures Department/employee which/who executes import procedures.
DL	Delivery contact Department/person responsible for delivery.
ED	Engineering contact Department/person to contact for matters regarding engineering.

Used Codes

GR	Goods receiving contact
	Department/person responsible for receiving the goods at the place of delivery.
HE	Emergency dangerous goods contact
	Party who is to be contacted to intervene in case of emergency.
HG	Dangerous goods contact
	Department/person to be contacted for details about the transportation of dangerous goods/hazardous material.
IC	Information contact
	Department/person to contact for questions regarding transactions.
LO	Place of collection contact
	Department/employee to be contacted at the place of collection.
MGR	Manager (GS1 Temporary Code)
	Person responsible for management within a department or company.
NT	Notification contact
	Department/employee to be notified.
OC	Order contact
	An individual to contact for questions regarding this order.
PD	Purchasing contact
	Department/person responsible for issuing this purchase order.
PM	Product management contact
	Department/person to contact for questions regarding this order.
QC	Quality coordinator contact
	Quality coordinator contact within an organization.
SA	Sales administration
	Name of the sales administration contact within a corporation.
SD	Shipping contact
	The shipping department contact within an organization.
SR	Sales representative or department
	The sales representative or department contact within an organization.
TA	Traffic administrator
	The traffic administrator contact within an organization.
TD	Test contact
	Department/person responsible for testing contact.
TR	Transport contact
	Department/person in charge of transportation.
WH	Warehouse
	The warehouse contact within an organization.

Used Codes

3155	Communication address code qualifier Code qualifying the communication address.
AL	Cellular phone Identifies the cellular phone number.
AO	Uniform Resource Location (URL) Identification of the Uniform Resource Location (URL) Synonym: World wide web address. EDIFACT
AQ	X.400 address for mail text The X.400 address accepting information in the body text of a message.
AR	AS1 address Address capable of receiving messages in accordance with the EDIINT/AS1 protocol for MIME based EDI .
AS	AS2 address Address capable of receiving messages in accordance with the EDIINT/AS2 protocol.
AT	AS3 address Address capable of receiving messages in accordance with the EDIINT/AS3 protocol.
AU	File Transfer Protocol Address capable for receiving message in accordance with the File Transfer Protocol (IETF RFC 959 et. al.).
CA	Cable address The communication number identifies a cable address.
EI	EDI Number identifying the service and service user.
EM	Electronic mail Exchange of mail by electronic means. GS1 Description: Creating/sending/receiving of unstructured free text messages or documents using computer network, a mini-computer or an attached modem and regular telephone line or other electronic transmission media.
EXI	Exite mail (GS1 Temporary Code) Requests that the file shall be returned via Exite. GS1 Note: Code marked for deletion.
FX	Fax Device used for transmitting and reproducing fixed graphic material (as printing) by means of signals over telephone lines or other electronic transmission media.

Used Codes

IA	Interchange address (GS1 Temporary Code) Code identifying an EDI interchange address.
TE	Telephone Voice/data transmission by telephone.
TL	Telex Transmission of text/data via telex.
XF	X.400 The X.400 address. GS1 Description: CCITT Message handling system.
XG	Pager Identifies that the communication number is for a pager.

3207	Country name code | Identification of the name of the country or other geographical entity as defined in ISO 3166-1. Notes: | 1. Use ISO 3166-1 two alpha country code.
AD	Andorra
AE	United Arab Emirates
AF	Afghanistan
AG	Antigua and Barbuda
AI	Anguilla
AL	Albania
AM	Armenia
AO	Angola
AQ	Antarctica
AR	Argentina
AS	American Samoa
AT	Austria
AU	Australia
AW	Aruba
AX	Åland Islands
AZ	Azerbaijan
BA	Bosnia and Herzegovina
BB	Barbados

Used Codes

BD	Bangladesh
BE	Belgium
BF	Burkina Faso
BG	Bulgaria
BH	Bahrain
BI	Burundi
BJ	Benin
BL	Saint Barthélemy
BM	Bermuda
BN	Brunei Darussalam
BO	Bolivia (Plurinational State of)
BQ	Bonaire, Sint Eustatius and Saba
BR	Brazil
BS	Bahamas
BT	Bhutan
BV	Bouvet Island
BW	Botswana
BY	Belarus
BZ	Belize
CA	Canada
CC	Cocos (Keeling) Islands
CD	Congo, Democratic Republic of
CF	Central African Republic
CG	Congo
CH	Switzerland
CI	Cote D'Ivoire
CK	Cook Islands
CL	Chile
CM	Cameroon
CN	China
CO	Colombia
CR	Costa Rica
CU	Cuba

Used Codes

CV	Cape Verde
CW	Curaçao
CX	Christmas Island
CY	Cyprus
CZ	Czechia
DE	Germany
DJ	Djibouti
DK	Denmark
DM	Dominica
DO	Dominican Republic
DZ	Algeria
EC	Ecuador
EE	Estonia
EG	Egypt
EH	Western Sahara
ER	Eritrea
ES	Spain
ET	Ethiopia
FI	Finland
FJ	Fiji
FK	Falkland Islands (Malvinas)
FM	Micronesia (Federated States of)
FO	Faroe Islands
FR	France
GA	Gabon
GB	United Kingdom of Great Britain and Northern Ireland
GD	Grenada
GE	Georgia
GF	French Guiana
GG	Guernsey
GH	Ghana
GI	Gibraltar
GL	Greenland

Used Codes

GM	Gambia
GN	Guinea
GP	Guadeloupe
GQ	Equatorial Guinea
GR	Greece
GS	South Georgia and the South Sandwich Islands
GT	Guatemala
GU	Guam
GW	Guinea-Bissau
GY	Guyana
HK	Hong Kong
HM	Heard Island and Mcdonald Islands
HN	Honduras
HR	Croatia
HT	Haiti
HU	Hungary
ID	Indonesia
IE	Ireland
IL	Israel
IM	Isle Of Man
IN	India
IO	British Indian Ocean Territory
IQ	Iraq
IR	Iran (Islamic Republic of)
IS	Iceland
IT	Italy
JE	Jersey
JM	Jamaica
JO	Jordan
JP	Japan
KE	Kenya
KG	Kyrgyzstan
KH	Cambodia

Used Codes

KI	Kiribati
KM	Comoros
KN	Saint Kitts and Nevis
KP	Korea (Democratic People'S Republic of)
KR	Korea, Republic of
KW	Kuwait
KY	Cayman Islands
KZ	Kazakhstan
LA	Lao People'S Democratic Republic
LB	Lebanon
LC	Saint Lucia
LI	Liechtenstein
LK	Sri Lanka
LR	Liberia
LS	Lesotho
LT	Lithuania
LU	Luxembourg
LV	Latvia
LY	Libya
MA	Morocco
MC	Monaco
MD	Moldova, Republic of
ME	Montenegro
MF	Saint Martin (French Part)
MG	Madagascar
MH	Marshall Islands
MK	Macedonia, the Former Yugoslav Republic of
ML	Mali
MM	Myanmar
MN	Mongolia
MO	Macao
MP	Northern Mariana Islands
MQ	Martinique

Used Codes

MR	Mauritania
MS	Montserrat
MT	Malta
MU	Mauritius
MV	Maldives
MW	Malawi
MX	Mexico
MY	Malaysia
MZ	Mozambique
NA	Namibia
NC	New Caledonia
NE	Niger
NF	Norfolk Island
NG	Nigeria
NI	Nicaragua
NL	Netherlands
NO	Norway
NP	Nepal
NR	Nauru
NU	Niue
NZ	New Zealand
OM	Oman
PA	Panama
PE	Peru
PF	French Polynesia
PG	Papua New Guinea
PH	Philippines
PK	Pakistan
PL	Poland
PM	Saint Pierre and Miquelon
PN	Pitcairn
PR	Puerto Rico
PS	Palestine, State of

Used Codes

PT	Portugal
PW	Palau
PY	Paraguay
QA	Qatar
RE	Reunion
RO	Romania
RS	Serbia
RU	Russian Federation
RW	Rwanda
SA	Saudi Arabia
SB	Solomon Islands
SC	Seychelles
SD	Sudan
SE	Sweden
SG	Singapore
SH	Saint Helena, Ascension and Tristan da Cunha
SI	Slovenia
SJ	Svalbard and Jan Mayen
SK	Slovakia
SL	Sierra Leone
SM	San Marino
SN	Senegal
SO	Somalia
SR	Suriname
SS	South Sudan
ST	Sao Tome and Principe
SV	El Salvador
SX	Sint Maarten (Dutch part)
SY	Syrian Arab Republic
SZ	Swaziland
TC	Turks and Caicos Islands
TD	Chad
TF	French Southern Territories

Used Codes

TG	Togo
TH	Thailand
TJ	Tajikistan
TK	Tokelau
TL	Timor-Leste
TM	Turkmenistan
TN	Tunisia
TO	Tonga
TR	Turkey
TT	Trinidad and Tobago
TV	Tuvalu
TW	Taiwan, Province of China
TZ	Tanzania, United Republic of
UA	Ukraine
UG	Uganda
UM	United States Minor Outlying Islands
US	United States of America
UY	Uruguay
UZ	Uzbekistan
VA	Holy See
VC	Saint Vincent and the Grenadines
VE	Venezuela (Bolivarian Republic of)
VG	Virgin Islands, British
VI	Virgin Islands, U.S.
VN	Viet Nam
VU	Vanuatu
WF	Wallis and Futuna
WS	Samoa
YE	Yemen
YT	Mayotte
ZA	South Africa
ZM	Zambia
ZW	Zimbabwe

Used Codes

3453	Language name code Code specifying the language name. Notes: 1. Use ISO 639-1988.
AA	Afar
aa	Afar
AB	Abkhazian
ab	Abkhazian
AE	Avestan
ae	Avestan
AF	Afrikaans
af	Afrikaans
AK	Akan
ak	Akan
AM	Amharic
am	Amharic
AN	Aragonese
an	Aragonese
AR	Arabic
ar	Arabic
AS	Assamese
as	Assamese
AV	Avaric
av	Avaric
AY	Aymara
ay	Aymara
AZ	Azerbaijani
az	Azerbaijani
BA	Bashkir
ba	Bashkir
BE	Belarusian
be	Belarusian
BG	Bulgarian
bg	Bulgarian

Used Codes

BH	Bihari
bh	Bihari
BI	Bislama
bi	Bislama
BM	Bambara
bm	Bambara
BN	Bengali
bn	Bengali
BO	Tibetan
bo	Tibetan
BR	Breton
br	Breton
BS	Bosnian
bs	Bosnian
CA	Catalan; Valencian
ca	Catalan; Valencian
CE	Chechen
ce	Chechen
CH	Chamorro
ch	Chamorro
CO	Corsican
co	Corsican
CR	Cree
cr	Cree
CS	Czech
cs	Czech
CU	Church Slavic; Old Slavonic; Church Slavonic; Old Bulgarian; Old Church Slavonic
cu	Church Slavic; Old Slavonic; Church Slavonic; Old Bulgarian; Old Church Slavonic
CV	Chuvash
cv	Chuvash
CY	Welsh
cy	Welsh

Used Codes

DA	Danish
da	Danish
DE	German
de	German
DV	Divehi; Dhivehi; Maldivian
dv	Divehi; Dhivehi; Maldivian
DZ	Dzongkha
dz	Dzongkha
EE	Ewe
ee	Ewe
EL	Greek; Modern (1453-)
el	Greek; Modern (1453-)
EN	English
en	English
EO	Esperanto
eo	Esperanto
ES	Spanish; Castilian
es	Spanish; Castilian
ET	Estonian
et	Estonian
EU	Basque
eu	Basque
FA	Persian
fa	Persian
FF	Fulah
ff	Fulah
FI	Finnish
fi	Finnish
FJ	Fijian
fj	Fijian
FO	Faroese
fo	Faroese
FR	French

Used Codes

fr	French
FY	Western Frisian
fy	Western Frisian
GA	Irish
ga	Irish
GD	Gaelic; Scottish Gaelic
gd	Gaelic; Scottish Gaelic
GL	Galician
gl	Galician
GN	Guarani
gn	Guarani
GU	Gujarati
gu	Gujarati
GV	Manx
gv	Manx
HA	Hausa
ha	Hausa
HE	Hebrew
he	Hebrew
HI	Hindi
hi	Hindi
HO	Hiri Motu
ho	Hiri Motu
HR	Croatian
hr	Croatian
HT	Haitian; Haitian Creole
ht	Haitian; Haitian Creole
HU	Hungarian
hu	Hungarian
HY	Armenian
hy	Armenian
HZ	Herero
hz	Herero

Used Codes

IA	Interlingua (International Auxiliary Language Association)
ia	Interlingua (International Auxiliary Language Association)
ID	Indonesian
id	Indonesian
IE	Interlingue
ie	Interlingue
IG	Igbo
ig	Igbo
II	Sichuan Yi
ii	Sichuan Yi
IK	Inupiaq
ik	Inupiaq
IO	Ido
io	Ido
IS	Icelandic
is	Icelandic
IT	Italian
it	Italian
IU	Inuktiut
iu	Inuktiut
JA	Japanese
ja	Japanese
JV	Javanese
jv	Javanese
KA	Georgian
ka	Georgian
KG	Kongo
kg	Kongo
KI	Kikuyu; Gikuyu
ki	Kikuyu; Gikuyu
KJ	Kuanyama; Kwanyama
kj	Kuanyama; Kwanyama
KK	Kazakh

Used Codes

kk	Kazakh
KL	Kalaallisut; Greenlandic
kl	Kalaallisut; Greenlandic
KM	Central Khmer
km	Central Khmer
KN	Kannada
kn	Kannada
KO	Korean
ko	Korean
KR	Kanuri
kr	Kanuri
KS	Kashmiri
ks	Kashmiri
KU	Kurdish
ku	Kurdish
KV	Komi
kv	Komi
KW	Cornish
kw	Cornish
KY	Kirghiz; Kyrgyz
ky	Kirghiz; Kyrgyz
LA	Latin
la	Latin
LB	Luxembourgish; Letzeburgesch
lb	Luxembourgish; Letzeburgesch
LG	Ganda
lg	Ganda
LI	Limburgan; Limburger; Limburgish
li	Limburgan; Limburger; Limburgish
LN	Lingala
ln	Lingala
LO	Lao
lo	Lao

Used Codes

LT	Lithuanian
lt	Lithuanian
LU	Luba-Katanga
lu	Luba-Katanga
LV	Latvian
lv	Latvian
MG	Malagasy
mg	Malagasy
MH	Marshallese
mh	Marshallese
MI	Maori
mi	Maori
MK	Macedonian
mk	Macedonian
ML	Malayalam
ml	Malayalam
MN	Mongolian
mn	Mongolian
MO	Moldavian; Moldovan
mo	Moldavian; Moldovan
MR	Marathi
mr	Marathi
MS	Malay
ms	Malay
MT	Maltese
mt	Maltese
MY	Burmese
my	Burmese
NA	Nauru
na	Nauru
NB	Bokmal Norwegian; Norwegian Bokmal
nb	Bokmal Norwegian; Norwegian Bokmal
ND	Ndebele; North; North Ndebele

Used Codes

nd	Ndebele; North; North Ndebele
NE	Nepali
ne	Nepali
NG	Ndonga
ng	Ndonga
NL	Dutch; Flemish
nl	Dutch; Flemish
NN	Norwegian Nynorsk; Nynorsk, Norwegian
nn	Norwegian Nynorsk; Nynorsk, Norwegian
NO	Norwegian
no	Norwegian
NR	Ndebele; South; South Ndebele
nr	Ndebele; South; South Ndebele
NV	Navajo; Navaho
nv	Navajo; Navaho
NY	Chichewa; Chewa; Nyanja
ny	Chichewa; Chewa; Nyanja
OC	Occitan (post 1500); Provencal
oc	Occitan (post 1500); Provencal
OJ	Ojibwa
oj	Ojibwa
OM	Oromo
om	Oromo
OR	Oriya
or	Oriya
OS	Ossetian; Ossetic
os	Ossetian; Ossetic
PA	Panjabi; Punjabi
pa	Panjabi; Punjabi
PI	Pali
pi	Pali
PL	Polish
pl	Polish

Used Codes

PS	Pushto; Pashto
ps	Pushto; Pashto
PT	Portuguese
pt	Portuguese
QU	Quechua
qu	Quechua
RM	Romansh
rm	Romansh
RN	Rundi
rn	Rundi
RO	Romanian
ro	Romanian
RU	Russian
ru	Russian
RW	Kinyarwanda
rw	Kinyarwanda
SA	Sanskrit
sa	Sanskrit
SC	Sardinian
sc	Sardinian
SD	Sindhi
sd	Sindhi
SE	Northern Sami
se	Northern Sami
SG	Sango
sg	Sango
SI	Sinhala; Sinhalese
si	Sinhala; Sinhalese
SK	Slovak
sk	Slovak
SL	Slovenian
sl	Slovenian
SM	Samoan

Used Codes

sm	Samoan
SN	Shona
sn	Shona
SO	Somali
so	Somali
SQ	Albanian
sq	Albanian
SR	Serbian
sr	Serbian
SS	Swati
ss	Swati
ST	Sotho, Southern
st	Sotho, Southern
SU	Sundanese
su	Sundanese
SV	Swedish
sv	Swedish
SW	Swahili
sw	Swahili
TA	Tamil
ta	Tamil
TE	Telugu
te	Telugu
TG	Tajik
tg	Tajik
TH	Thai
th	Thai
TI	Tigrinya
ti	Tigrinya
TK	Turkmen
tk	Turkmen
TL	Tagalog
tl	Tagalog

Used Codes

TN	Tswana
tn	Tswana
TO	Tonga (Tonga Islands)
to	Tonga (Tonga Islands)
TR	Turkish
tr	Turkish
TS	Tsonga
ts	Tsonga
TT	Tatar
tt	Tatar
TW	Twi
tw	Twi
TY	Tahitian
ty	Tahitian
UG	Uighur; Uyghur
ug	Uighur; Uyghur
UK	Ukrainian
uk	Ukrainian
UR	Urdu
ur	Urdu
UZ	Uzbek
uz	Uzbek
VE	Venda
ve	Venda
VI	Vietnamese
vi	Vietnamese
VO	Volapük
vo	Volapük
WA	Walloon
wa	Walloon
WO	Wolof
wo	Wolof
XH	Xhosa

Used Codes

xh	Xhosa
YI	Yiddish
yi	Yiddish
YO	Yoruba
yo	Yoruba
ZA	Zhuang; Chuang
za	Zhuang; Chuang
ZH	Chinese
zh	Chinese
ZU	Zulu
zu	Zulu

4343	Response type code Code specifying the type of acknowledgment required or transmitted.
AA	Debit advice Receiver of the payment message needs to return a debit advice in response to the payment message.
AB	Message acknowledgement Indicates that an acknowledgement relating to receipt of message is required.
AC	Acknowledge - with detail and change Acknowledge complete including changes.
AI	Acknowledge only changes Acknowledgement of changes only is required.
AJ	Pending Indication that the referenced offer or transaction (e.g. cargo booking or quotation request) is being dealt with. EDIFACT
AP	Accepted Indication that the referenced offer or transaction (e.g., cargo booking or quotation request) has been accepted.
AS	Credit advice and message acknowledgement The receiver of the message is to acknowledge receipt of the message and sent a credit advice for each credit.
CA	Conditionally accepted Indication that the referenced offer or transaction (e.g., cargo booking or quotation request) has been accepted under conditions indicated in this message.

Used Codes

NA	No acknowledgement needed Specifies that no acknowledgement is needed in response to this message.
RE	Rejected Indication that the referenced offer or transaction (e.g., cargo booking or quotation request) is not accepted.
YW7	Credit advice (SWIFT Code) Receiver of the payment message needs to return a credit advice in response to the payment message.

4441	Free text value code Code specifying free form text.
78E	Proof Of Delivery (GS1 Permanent Code) The mentioned URL refers to a Proof of Delivery document. This Code value can be used if DE 4451 of the FTX segment is ZXL.

4451	Text subject code qualifier Code qualifying the subject of the text.
1E	Additional product information address (GS1 Temporary Code) Address at which additional information on the product can be found. GS1 Note: Code marked for deletion. Use value BAI instead.
2E	VAT exemption (GS1 Temporary Code) VAT exemption reason in clear text. GS1 Note: Code marked for deletion. Use value BAQ instead.
3E	Tracking URL (GS1 Temporary Code) The internet link (URL) to track the delivery of a specific package or consignment.
AAA	Goods description [7002] Plain language description of the nature of the goods sufficient to identify them at the level required for banking, Customs, statistical or transport purposes, avoiding unnecessary detail (Generic term).
AAB	Terms of payments [4276] Conditions of payment between the parties to a transaction (generic term).
AAC	Dangerous goods additional information Additional information concerning dangerous goods.
AAD	Dangerous goods, technical name Proper shipping name, supplemented as necessary with the correct technical name, by which a dangerous substance or article may be correctly identified or which is sufficiently informative to permit identification by reference to generally available literature.

Used Codes

AAG	Party instructions
	Indicates that the segment contains instructions to be passed on to the identified party.
AAI	General information
	The text contains general information.
AAK	Price conditions
	Information on the price conditions that are expected or given.
AAM	Equipment re-usage restrictions
	Technical or commercial reasons why a piece of equipment may not be re-used after the current transport terminates.
AAN	Handling restriction
	Restrictions in handling depending on the technical characteristics of the piece of equipment or on the nature of the goods.
AAO	Error description (free text)
	Error described by a free text.
AAR	Terms of delivery
	(4053) Free text of the non Incoterms terms of delivery. For Incoterms, use: 4053.
AAW	Letter of credit information
	Information pertaining to the letter of credit.
AAZ	Additional export information
	The text contains additional export information.
ABN	Accounting information
	Self explanatory.
	GS1 Description:
	Free text information regarding account.
ABO	Discrepancy information
	Free text or coded information to indicate a specific discrepancy.
ABU	Deferred payment termed additional
	Additional terms concerning deferred payment.
ACB	Additional information
	The text contains additional information.
ACD	Reason
	Reason for a request or response.
ACE	Dispute
	A notice, usually from buyer to seller, that something was found wrong with goods delivered or the services rendered, or with the related invoice.

Used Codes

ACF	Additional attribute information The text refers to information about an additional attribute not otherwise specified.
ACL	Quality Statement Code A statement on the quality of an object.
ADK	Promotion information The text contains information about a promotion.
ADL	Meter condition Description of the condition of a meter.
ADM	Meter reading information Information related to a particular reading of a meter.
ADS	Booked item information (SWIFT Code) Information pertaining to a booked item. GS1 Description: Information related to an item booked onto a financial account.
AEI	Instructions to the applicant Instructions given to the applicant.
AFF	Batch code structure A description of the structure of a batch code.
AFG	Product application A general description of the application of a product.
AGW	Location Description of a location.
AGZ	Marketing activities Information concerning marketing activities.
AIP	Question A free text question.
AIQ	Party information Free text information related to a party.
AIX	Warranty terms Text describing the terms of warranty which apply to a product or service.
ALL	All documents The note implies to all documents.
BAI	Additional product information address Address at which additional information on the product can be found. GS1 Note: Replaces GS1 Temporary Code 1E.

Used Codes

BAJ	**Information to be printed on despatch advice** Specification of free text information which is to be printed on a despatch advice. GS1 Note: Replaces GS1 Temporary Code DSI.
BAK	**Missing goods remarks** Remarks concerning missing goods. GS1 Note: Replaces GS1 Temporary Code MIS.
BAL	**Non-acceptance information** Information related to the non-acceptance of an order, goods or a consignment. GS1 Note: Replaces GS1 Temporary Code NAI.
BAM	**Returns information** Information related to the return of items. GS1 Note: Replaces GS1 Temporary Code RTI.
BAN	**Sub-line item** Note contains information related to sub-line item data. GS1 Note: Replaces GS1 Temporary Code SID.
BAO	**Test information** Information of a test. GS1 Note: Replaces GS1 Temporary Code TIN.
BAP	**External link** The external link to a digital document (e.g.: URL) GS1 Note: Replaces GS1 Temporary Code ZXL.
BAQ	**VAT exemption reason** The reason for Value Added Tax exemption. GS1 Note: Replaces GS1 Temporary Code 2E.
BLR	**Transport document remarks** Remarks concerning the complete consignment to be printed on the bill of lading.
BLV	**B2C marketing information, short description** Consumer marketing information, short description.
BLW	**B2B marketing information, long description** Trading partner marketing information, long description.
BLX	**B2C marketing information, long description** Consumer marketing information, long description.

Used Codes

BLY	Product ingredients
	Information on the ingredient make up of the product.
	Information on the constituent ingredient make up of the product specified as one string.
	Example:
	FTX+ING+1+ +Tomato puree (54%), water, onions (9%), sunflower seed oil'
	FTX+ING+1+ +(cold pressed, untempered, unrefined) (10%), corn syrup (2%), soy protein (12%) ...:...:::+EN'
CHG	Change information
	Note contains change information.
CIP	Customs clearance instruction import
	Any coded or clear instruction agreed by customer and carrier regarding the import declaration of the goods.
CLR	Loading remarks
	Instructions concerning the loading of the container.
CUS	Customs declaration information
	Note contains customs declaration information.
DAR	Damage remarks
	Remarks concerning damage on the cargo.
DEL	Delivery information
	Information about delivery.
DIN	Delivery instructions
	Instructions regarding the delivery of the cargo.
DSI	Information to be printed on despatch advice (GS1 Temporary Code)
	Specification of free text information which is to be printed on a despatch advice.
	GS1 Note: Code marked for deletion. Use value BAJ instead.
DUT	Duty declaration
	The text contains a statement constituting a duty declaration.
GEN	Entire transaction set
	Note is general in nature, applies to entire transaction segment.
HAN	Handling instructions
	[4078] Instructions on how specified goods, packages or containers should be handled.
HAZ	Hazard information
	Information pertaining to a hazard.
IIN	Insurance instructions
	Instructions regarding the cargo insurance.

Used Codes

INS	Insurance information Specific note contains insurance information.
INV	Invoice instruction Note contains invoice instructions.
ITS	Testing instructions Instructions regarding the testing that is required to be carried out on the items in the transaction.
LIN	Line item Note contains line item information.
LOI	Loading instruction Instructions where specified packages or containers are to be loaded on a means of transport.
MIS	Missing goods remarks (GS1 Temporary Code) Remarks concerning missing goods. GS1 Note: Code marked for deletion. Use value BAK instead.
MKS	Additional marks/numbers information Additional information regarding the marks and numbers.
NAI	Non-acceptance information (GS1 Temporary Code) Information related to the non-acceptance of an order, goods or a consignment. GS1 Note: Code marked for deletion. Use value BAL instead.
ORI	Order instruction Free text contains order instructions.
OSI	Other service information General information created by the sender of general or specific value.
PAC	Packing/marking information Information regarding the packaging and/or marking of goods.
PAY	Payables information Note contains payables information.
PKG	Packaging information Note contains packaging information. GS1 Description: Note contains packaging instructions.
PMD	Payment detail/remittance information The free text contains payment details.
PMT	Payment information Note contains payments information.
PRD	Product information The text contains product information.

Used Codes

PRF	Price calculation formula Additional information regarding the price formula used for calculating the item price.
PRI	Priority information Note contains priority information.
PUR	Purchasing information Note contains purchasing information.
QQD	Quality demands/requirements Specification of the quality/performance expectations or standards to which the items must conform.
QUT	Quotation instruction/information Note contains quotation information.
REG	Regulatory information The free text contains information for regulatory authority.
RET	Return to origin information Free text information on an IATA Air Waybill to indicate consignment returned because of non delivery.
REV	Receivables The text contains receivables information.
RQR	Requested routes/routing instructions [3074] Names of places via which the consignor requests a consignment to be routed.
RQT	Tariffs and route requested [4120] Stipulation of the tariffs to be applied showing, where applicable, special-agreement numbers or references; indication of routes by frontier points or by frontier stations and, when necessary, by transit stations between.
RTI	Returns information (GS1 Temporary Code) Information related to the return of goods. GS1 Note: Code marked for deletion. Use value BAM instead.
SAF	Safety information The text contains safety information.
SIC	Sender's instruction to carrier [4284] Instructions given and declarations made by the sender to the carrier concerning Customs, insurance, and other formalities.
SID	Sub line item (GS1 Temporary Code) Note contains information related to sub line item data. GS1 Note: Code marked for deletion. Use value BAN instead.
SIN	Special instructions Special instructions like licence no, high value, handle with care, glass.

Used Codes

SPH	Special handling Note contains special handling information.
SSR	Special service request Request for a special service concerning the transport of the goods.
SUR	Supplier remarks Remarks from or for a supplier of goods or services.
TIN	Test information (GS1 Temporary Code) Information related to a test which will be, or has been, carried out. GS1 Note: Code marked for deletion. Use value BAO instead.
TRA	Transportation information General information regarding the transport of the cargo.
TXD	Tax declaration The text contains a statement constituting a tax declaration.
WHI	Warehouse instruction/information Note contains warehouse information.
XYZ	No partial delivery (GS1 Temporary Code) The goods that are not delivered have to be re-ordered by the buyer. Supplier only delivers the goods they have in stock at that moment. One order leads to one delivery.
ZXL	External link (GS1 Temporary code) The external link to a digital document (e.g.: URL) GS1 Note 1: This Code value can be used if no EFI segment is available. If the type of the referenced document (e.g. proof-of-delivery.pdf) can be identified by a code value of DE 1001, this code value should be used to fill DE 4441. (e.g. 78E), DE 3055 = 9. GS1 Note 2: Code marked for deletion. Use value BAP instead.
ZYZ	Partial delivery allowed (GS1 Temporary Code) The supplier keeps delivering until the entire order is fulfilled. One order can lead to many deliveries. The buyer doesn't need to place a new order; they just waits for the other goods to be delivered.
ZZZ	Mutually defined Note contains information mutually defined by trading partners.

4453	Free text function code Code specifying the function of free text.
1	Text for subsequent use The occurrence of this text does not affect message processing.
2	Text replacing missing code Text description of a coded data item for which there is no currently available code.

Used Codes

3   Text for immediate use
           Text must be read before actioning message.

Example

UNA:+.? '	
	UNA:+.? '
UNB+UNOA:3+4012345000009:14:1+4000004000002:14:4000004000099+021013:1043 +12345555+REF:AA++A+1+EANCOM-DISI+1'	
	UNB+UNOA:3+5412345678908:14+8798765432106:14+020102: 1000+12345555+++++EANCOMREF 52'
UNH+1+GENRAL:D:01B:UN:EAN005'	
	UNH+ME000001+GENRAL:D:01B:UN:EAN005'
BGM+719::9:A+1+9+AA'	
	BGM+719::9+GE282+9'
DTM+137:19930906:102'	
	DTM+137:20020106:102'
RFF+BC:1'	
	RFF+ON:930625'
DTM+171:19930827:102'	
	DTM+171:20020827:102'
NAD+BY+5412345000013::9+X::::X+A:A:A:A:S:1+A:A:A:X+A+A:23:2:X+A+GB'	
	NAD+FR+5456789000017::9'
	NAD+MR+3323456007896::9'
RFF+VA:55344212'	
	RFF+VA:VR123554'
DTM+171:19930101:102'	
	DTM+171:20020827:102'
CTA+AD+ACCOUNTS:GEORGE BERRY'	
	CTA+SA+:GEORGE BERRY'
COM+00447185644221:TE'	
	COM+00447188755112:TE'
FTX+AAA+1+001:23:91+A:A:A:A:A+EN'	
	FTX+ADK+1++OUR STOREWIDE SPRING SALE WILL START NEXT WEEK:ALL ITEMS 10 TO 30 % OFF'
NAD+NI+1::9+X::::X+A:A:A:A:A:1+A:A:A:X+A+A:23:2:X+A+GB'	
	NAD+NI+3323456001238::9'
RFF+PD:1'	
	RFF+PD:324FEB97'
DTM+171:19930101:102'	
	DTM+171:20020101:102'
CTA+AA+1:1'	
	CTA+PM+:MARY DECKER'
COM+1:TE'	
	COM+00447188433211:FX'
UNT+17+1'	
	UNT+17+ME000001'
UNZ+1+12345555'	
	UNZ+5+12345555'

Example